

ROAD REPAIR AND ACCOUNTABILITY ACT OF 2017  
PROJECT BASELINE AGREEMENT

SJ SR-4 Pavement Resurfacing and Restoration (EA 10-1C500)

Resolution SHOPP - P - 1819 - 09B  
(will be completed by CTC)

**1. FUNDING PROGRAM**

- Active Transportation Program
- Local Partnership Program (Competitive)
- Solutions for Congested Corridors Program
- State Highway Operation and Protection Program
- Trade Corridor Enhancement Program

**2. PARTIES AND DATE**

2.1 This Project Baseline Agreement (Agreement) for the *SJ SR-4 Pavement Resurfacing and Restoration (EA 10-1C500)*, effective on, DECEMBER 6, 2018 (will be completed by CTC), is made by and between the California Transportation Commission (Commission), the California Department of Transportation (Caltrans), the Project Applicant, *Caltrans*, and the Implementing Agency, *Caltrans*, sometimes collectively referred to as the "Parties".

**3. RECITAL**

- 3.2 Whereas at its March 22, 2018 meeting the Commission approved the State Highway Operation and Protection Program, and included in this program of projects the *SJ SR-4 Pavement Resurfacing and Restoration (EA 10-1C500)*, the parties are entering into this Project Baseline Agreement to document the project cost, schedule, scope and benefits, as detailed on the Project Programming Request Form attached hereto as Exhibit A and the Project Report attached hereto as Exhibit B, as the baseline for project monitoring by the Commission.
- 3.3 The undersigned Project Applicant certifies that the funding sources cited are committed and expected to be available; the estimated costs represent full project funding; and the scope and description of benefits is the best estimate possible.

**4. GENERAL PROVISIONS**

The Project Applicant, Implementing Agency, and Caltrans agree to abide by the following provisions:

- 4.1 To meet the requirements of the Road Repair and Accountability Act of 2017 (Senate Bill [SB] 1, Chapter 5, Statutes of 2017) which provides the first significant, stable, and on-going increase in state transportation funding in more than two decades.
- 4.2 To adhere, as applicable, to the provisions of the Commission:
  - Resolution *Insert Number*, "Adoption of Program of Projects for the Active Transportation Program", dated
  - Resolution *Insert Number*, "Adoption of Program of Projects for the Local Partnership Program", dated
  - Resolution *Insert Number*, "Adoption of Program of Projects for the Solutions for Congested Corridors Program", dated
  - Resolution G-18-13, "Adoption of Program of Projects for the State Highway Operation and Protection Program", dated March 22, 2018
  - Resolution *Insert Number*, "Adoption of Program of Projects for the Trade Corridor Enhancement Program", dated

- 4.3 All signatories agree to adhere to the Commission's State Highway Operation and Protection Program, Guidelines. Any conflict between the programs will be resolved at the discretion of the Commission.
- 4.4 All signatories agree to adhere to the Commission's SB 1 Accountability and Transparency Guidelines and policies, and program and project amendment processes.
- 4.5 Caltrans agrees to secure funds for any additional costs of the project.
- 4.6 Caltrans agrees to report on a quarterly basis; after July 2019, reports will be on a semi-annual basis on the progress made toward the implementation of the project, including scope, cost, schedule, outcomes, and anticipated benefits.
- 4.7 Caltrans agrees to prepare program progress reports on a quarterly basis; after July 2019, reports will be on a semi-annual basis and include information appropriate to assess the current state of the overall program and the current status of each project identified in the program report.
- 4.8 Caltrans agrees to submit a timely Completion Report and Final Delivery Report as specified in the Commission's SB 1 Accountability and Transparency Guidelines.
- 4.9 All signatories agree to maintain and make available to the Commission and/or its designated representative, all work related documents, including without limitation engineering, financial and other data, and methodologies and assumptions used in the determination of project benefits during the course of the project, and retain those records for four years from the date of the final closeout of the project. Financial records will be maintained in accordance with Generally Accepted Accounting Principles.
- 4.10 The Transportation Inspector General of the Independent Office of Audits and Investigations has the right to audit the project records, including technical and financial data, of the Department of Transportation, the Project Applicant, the Implementing Agency, and any consultant or sub-consultants at any time during the course of the project and for four years from the date of the final closeout of the project, therefore all project records shall be maintained and made available at the time of request. Audits will be conducted in accordance with Generally Accepted Government Auditing Standards.

## 5. SPECIFIC PROVISIONS AND CONDITIONS

- 5.1 Project Schedule and Cost  
See Project Programming Request Form, attached as Exhibit A.
- 5.2 Project Scope  
See Project Report or equivalent, attached as Exhibit B. At a minimum, the attachment shall include the cover page, evidence of approval, executive summary, and a link to or electronic copy of the full document.
- 5.3 Other Project Specific Provisions and Conditions


### Attachments:

- Exhibit A: Project Programming Request Form  
Exhibit B: Project Report


SIGNATURE PAGE  
TO  
PROJECT BASELINE AGREEMENT

SJ SR 4 Pavement Resurfacing and Restoration (EA 10-1C500)

Resolution SHOPP-P-1819-09B

  
\_\_\_\_\_  
Dennis T. Agar  
District Director  
California Department of Transportation

10/15/18  
Date

  
\_\_\_\_\_  
Laurie Berman  
Director  
California Department of Transportation

11-6-18  
Date

  
\_\_\_\_\_  
Susan Bransen  
Executive Director  
California Transportation Commission

12/13/18  
Date

Baseline agreement information was extracted from Caltrans' project data systems. Project description, funding and performance measures are from CTIPS. Project delivery milestones are from PRSM. All information is current and accurate.

## STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION

## BASELINE AGREEMENT

Date: 11/06/18 11:12:44 AM

District	EA	Project ID		PPNO	Project Manager		
10	1C500	1016000026		3165	PADDA, JESKRN S		
County	Route	Begin Postmile	End Postmile	Implementing Agency			
SJ	4	T 15.5	R 16.7	PA&ED	Caltrans		
				PS&E	Caltrans		
				Right of Way	Caltrans		
				Construction	Caltrans		
<b>Project Nickname</b>							
SJ SR 4 Pavement Resurfacing and Restoration							
<b>Location/Description</b>							
In Stockton, from 0.2 mile east of Fresno Avenue to Center Street; also on Route 5 from Taylor Street Overhead to Stockton Channel Viaduct (PM 25.8/26.5). Roadway rehabilitation.							
<b>Legislative Districts</b>							
<b>Assembly:</b>	26		<b>Senate:</b>	05		<b>Congressional:</b>	11
<b>PERFORMANCE MEASURES</b>							
	<b>Primary Asset</b>	<b>Good</b>	<b>Fair</b>	<b>Poor</b>	<b>New</b>	<b>Total</b>	<b>Units</b>
Existing Condition	Pavement	0.71	0.84	3.1		4.65	Lane-miles
Programmed Condition	Pavement	4.65				4.65	Lane-miles
<b>Project Milestone</b>						<b>Actual</b>	<b>Planned</b>
Project Approval and Environmental Document Milestone						05/09/18	
Right of Way Certification Milestone							10/10/19
Ready to List for Advertisement Milestone							11/10/19
Begin Construction Milestone (Approve Contract)							07/11/20
<b>FUNDING (Allocated amounts are shaded)</b>							
<b>Component</b>	<b>Fiscal Year</b>	<b>SHOPP</b>					<b>Total</b>
PA&ED	17/18	538					538
PS&E	18/19	2,478					2,478
RW Support	18/19	19					19
Const Support	19/20	4,979					4,979
RW Capital	19/20	48					48
Const Capital	19/20	35,157					35,157
<b>Total</b>		<b>43,219</b>					<b>43,219</b>



# Project Report


## *For Project Approval*

On Route 4

Between From 0.1 Mile East of Fresno Avenue


And Central Viaduct

I have reviewed the right-of-way information contained in this report and the right-of-way data sheet attached hereto, and find the data to be complete, current and accurate:




JAMIE LUPO,  
CENTRAL REGION Division Chief, Right of Way

APPROVAL RECOMMENDED:



JES PADDA, Project Manager

PROJECT APPROVED:




DENNIS T. AGAR, District Director

05/09/18

Date




This project report has been prepared under the direction of the following registered civil engineer. The registered civil engineer attests to the technical information contained herein and the engineering data upon which recommendations, conclusions, and decisions are based.



REGISTERED CIVIL ENGINEER

4/10/18

DATE



## Table of Contents

	PAGE
1 INTRODUCTION	1
2 RECOMMENDATION	1
3 BACKGROUND	1
4 PURPOSE AND NEED	2
5 ALTERNATIVES	6
6 CONSIDERATIONS REQUIRING DISCUSSION	7
7 OTHER CONSIDERATIONS AS APPROPRIATE	8
8 FUNDING, PROGRAMMING AND ESTIMATE	10
9 DELIVERY SCHEDULE	11
10 RISKS	11
11 EXTERNAL AGENCY COORDINATION	11
12 PROJECT REVIEWS	12
13 PROJECT PERSONNEL	12
14 ATTACHMENTS	12

## 1. INTRODUCTION

This is a resurfacing and restoration (2R) roadway rehabilitation project located on State Route (SR) 4 at the SR 4/I-5 interchange in the City of Stockton. The project will address pavement deterioration on SR 4 and on the connectors with Interstate 5 (I-5) and local street ramps.

The project is programmed in the 2018 State Highway Operation and Protection (SHOPP) for funding in the 2019/2020 fiscal year.

<b>Project Limits</b>	10-SJ-4 R15.5/R16.7	
<b>Number of Alternatives</b>	2	
	<b>Current Cost Estimate:</b>	<b>Escalated Cost Estimate:</b>
<b>Capital Outlay Support</b>	\$7,739,000	\$8,111,000
<b>Capital Outlay Construction</b>	\$31,162,000	\$33,835,000
<b>Capital Outlay Right-of-Way</b>	\$0	\$0
<b>Funding Source</b>	201.122	
<b>Funding Year</b>	2019/2020	
<b>Type of Facility</b>	4- and 6-lane freeway	
<b>Number of Structures</b>	0	
<b>SHOPP Project Output</b>	10 Lane-Miles	
<b>Environmental Determination or Document</b>	CE/CE	
<b>Legal Description</b>	In San Joaquin County In Stockton from 0.1 Mile east of Fresno Ave to Central viaduct	
<b>Project Development Category</b>	5	

## 2. RECOMMENDATION

It is recommended that this project report be approved and authorization be granted to proceed to the design phase with the build alternative.

## 3. BACKGROUND

A Project Scope Summary Report (PSSR) was approved on August 9, 2016 and the project was targeted for programming in the 2018 SHOPP for delivery in the 2021/22 fiscal year. However, delivery has been accelerated to the 2019/20 fiscal year due to availability of SB 1 funds.

This project is scoped as a 2R (resurfacing and restoration) project per the guidelines in Design Information Bulletin 79-03. The 2R Project Certification was approved on

December 21, 2015 (**Attachment J**). A Safety Analysis report was prepared as part of the 2R Certification, and concluded there were no apparent safety issues that need to be addressed through geometric improvements to the existing roadway. As per 2R guidelines, approvals of design exceptions are not required.

The SR 4/I-5 interchange was constructed in 1970 as a four-level interchange with eight freeway to freeway connectors. The interchange also includes four local street ramps (two on-ramps and two off-ramps). SR 4 within the project limits consists of 3 lanes in each direction but only two lanes are currently used for traffic in each direction. The recently completed segment to the west (SR 4 Crosstown Ramp Extension) constructed two lanes in each direction and extended the freeway approximately one mile to the west where the freeway terminates at Navy Drive. The segment to the east is known as the Crosstown Freeway and consists of three to four traffic lanes in each direction as the eastbound and westbound connectors with I-5 merge and diverge, respectively, with SR 4. The posted speed limit is 65 miles per hour.

#### **4. PURPOSE AND NEED**

##### **Purpose:**

The purpose of this project is to restore the pavement to a state of good repair, improve ride quality, extend the pavement service life and minimize maintenance costs and effort.

##### **Need:**

The existing portland cement concrete (PCC) pavement of SR 4 and all the freeway-to-freeway connectors have developed 3<sup>rd</sup> stage cracking, resulting in rough riding quality and increasing maintenance needs. Additionally the flexible pavement of the local street ramps and the shoulder pavement on the connectors have developed alligator cracking and a rough surface.

##### **A. Problem, Deficiencies, Justification**

The pavement will continue to deteriorate rapidly requiring extensive repairs and exposure of maintenance personnel to unsafe traffic conditions. The Pavement Condition Report (**Attachment I**) indicates the pavement has developed major structural distress.






Eastbound SR 4



Southbound I-5 to Eastbound SR 4 connector



Eastbound SR 4 to Southbound I-5 connector

## B. Regional and System Planning

SR 4 is classified as a Non-Interstate Strategic Highway Network (STRAHNET) route between I-5 and SR 99. West of I-5, SR 4 is part of the Interregional Road System (IRRS), classified as an intermodal connector. With the recent completion of the SR 4 Crosstown Ramp Extension project which removed the two ramps at Fresno Street and extended the freeway to Navy Drive, this segment of SR 4 provides a vital link to and from the Port of Stockton.

The 2014 Transportation Concept Report designates the segment of SR 4 west of I-5 to be an ultimate 4-lane freeway, while the segment east of I-5 is proposed to be an 8-lane freeway concept facility and a 10-lane freeway Ultimate Transportation Corridor. The current Level-of-Service (LOS) is “A” and the Concept LOS is “D”.

This project is included in the Caltrans 10-Year SHOPP Plan. Coordinated with other planned projects in the area will be required. The following are other planned projects in the vicinity of this project:

- |                                |   |
|--------------------------------|---|
| 10-0X690_ SJ-4- PM R15.7/19.2  | Roadside Safety Improvements.<br>Begin construction in July 2019.                       |
| 10-1C860_ SJ-4- PM R17.3/R17.4 | Reconstruct Hinge #32 (Crosstown Freeway Viaduct).<br>Begin construction in March 2020. |

10-1F180\_ SJ-4- PM R16.0/R19.4 Install Ramp Metering System on the westbound Center Street on-ramp. Begin construction in June 2022.

**C. Traffic**

Current and Forecasted Traffic:

Current (2016) ADT	<u>18,000</u>	
Construction Year (2021) ADT	<u>22,900</u>	10-Year ADT _____
DHV (2041)	<u>3,710</u>	ADT (2041) <u>37,100</u>
DHV (2061)	<u>6,100</u>	ADT (2061) <u>61,000</u>
D	<u>57%</u>	% Trucks <u>11.2%</u>
T.I. (10-Year)	_____	ESAL (10-Year) _____
T.I. (20-Year)	<u>12.5</u>	ESAL (20-Year) <u>15,407,657</u>
T.I. (40 – Year)	<u>14.0</u>	ESAL (40-Year) <u>39,326,847</u>

Note: ADT – Average Daily traffic; DHV – Design Hourly Volume; T.I. – Traffic Index; EASL – Equivalent Single Axle Loads; D – Direction

Collision Analysis:

The latest 3-Year (July 1, 2012 To June 30, 2015) Collision Data is shown below:

**Accident Rates (ACC/MVM)**  
10-SJ-4- PM R15.5/R16.6

	<b>Fatal</b>	<b>Fatal+Injury</b>	<b>Total</b>
Actual	0	0.33	0.58
Statewide Average	0.006	0.44	1.01

Note: ACC/MVM - accidents per million vehicle miles.

The actual accident rates were lower than the average rate for similar facilities. There were 28 collisions reported within the study period, including 16 “injury”, and no “fatal” accidents. Out of the 28 collisions, 20 were “rear end”, with “speeding” as the primary collision factor.

There were no “fatal” accidents on any of the connectors and ramps within the project limits. Only one location, the westbound SR 4 to southbound I-5 Connector, had a significantly high number and higher than average accident rates. There were a total of 34 accidents reported along the curved alignment of this connector, including 15 “run-off-road” and 9 “sideswipe” type accidents.



**Accident Rates (ACC/MV)**  
Westbound SR 4 to southbound I-5 Connector

	<b>Fatal</b>	<b>Fatal+Injury</b>	<b>Total</b>
Actual	0	0.67	1.75
Statewide Average	0.003	0.15	0.45

Note: ACC/MV - accidents per million vehicle.

To address the frequent run-off-road accidents on this connector, a project was initiated by the District Office of Traffic Safety and the project was constructed in 2016. It reconstructed the pavement and applied a high friction surface treatment. It also installed new advisory speed signs with flashing beacons, and lowered the advisory speed from 50 to 45 mph. The accident data shown above precedes the safety improvements constructed in 2016.

## 5. ALTERNATIVES

### 5A. Viable Alternative – Build Alternative

This alternative proposes to remove and replace the existing PCC pavement, asphalt concrete pavement and existing bridge approach slabs on Route 4 and all the ramps and connectors within the project limits.

Two optional pavement structural sections were considered; Continuous Reinforced Concrete Pavement (CRCP) and Crack Seal and Overlay (CSOL).

A Life Cycle Cost Analysis (LCCA) prepared in 2016 studied the main line of SR-4 to compare the two options. The LCCA concluded that over the 55-year analysis period, the CSOL option is \$600,000 less than the CRCP option.

The same LCCA studied the ramps and connectors, comparing the same two options of pavement type. The LCCA concluded that over the 55-year analysis period, CRCP is less costly than CSOL by approximately \$0.5-million.

Although the LCCA of the main lanes indicated that the CSOL option would cost approximately \$0.6-million less than the CRCP option, the CSOL option results in higher vertical profile grade and would require long transitions to conform to the existing bridge deck profiles. Raising the roadway profile would also reduce vertical bridge and overhead sign clearances. It would also require additional earthwork and temporary and permanent erosion control measures. In addition, it would also require extensive modifications of the existing drainage system. The resulting additional expense of the added earthwork and drainage modifications offset the potential savings in paving costs between the two options.

Based on the above analysis, the CRCP option, with 40 year pavement design life, is the preferred strategy. See Attachment B for the proposed pavement structural sections. The selected structural sections are based on HDM Table 623.1F, Rigid Pavement Catalog (Inland valley, Type 1 Subgrade Soil).

Existing drainage facilities include drainage inlets, culverts, downdrains, roadside ditches, detention ponds and pump stations. Most of the roadway run-off directly outfalls to Mormon Slough through an underground conveyance system. There are several spot locations with unacceptable spread on the travelled way that require installation of additional inlets and downdrains. Post construction permanent treatment of storm water runoff may be necessary and may require modifications to the drainage system to allow capture of sediment before entering Mormon Slough. The need and feasibility of such modifications will be determined during the early stages of design.

Existing metal beam guard rail, bridge approach rail and dike within the project limits will be brought up to current standards. All green roadside guide signs will be replaced with new panels made of high reflective sheeting material, and delineators, object markers and bridge information signs will be brought to current standards. Lighting will be upgraded and existing detector loops will be replaced.

#### **5B. Rejected Alternatives**

The no build alternative is rejected since it does not meet the purpose and need to restore the pavement to a state of good repair and minimize maintenance efforts and expenses.

### **6. CONSIDERATIONS REQUIRING DISCUSSION**

#### **6A. Hazardous Waste**

Treated wood removed from existing metal beam guardrail installation will need to be disposed of at a certified disposal facility. No other hazardous waste is anticipated. A preliminary site investigation (PSI) is not required to test the soil for hazardous materials since no soil is to be exported from the project site.

#### **6B. Value Analysis**

This project does not meet the criteria for a Value Analysis study.

#### **6C. Resource Conservation**

Removed concrete pavement will become the property of the construction contractor for possible recycling.

#### **6D. Right-of-Way Issues**

All work will be within existing right of way and no utility conflicts are anticipated. Underground utilities within the project limits are located under city streets and would not be impacted by replacing the pavement on SR 4 or the ramps and connectors. The right of way data sheet is attached (**Attachment F**).

**6E. Railroad Involvement:**

A branch of the Northern Burlington Santa Fe Railroad is within the project limits. The railroad crosses SR 4 at PM R15.8 (Garfield Street Overhead) and crosses I-5 at PM 25.8 (Taylor Street Overhead). Work on the bridge approach slabs at these two overheads should not interfere with the railroad operations. A minimum of 50 feet lateral clearance is available from the approach slabs to the nearest track.

**6F. Environmental Compliance**

The project has been Categorically Exempt under Class 1 of the California Environmental Quality Act guidelines and Categorically Excluded under the National Environmental Policy Act. The CE/CE is attached (**Attachment E**). The following avoidance and minimization measures would be implemented prior to and during construction:

- Conduct Environmental Awareness Training
- Return temporarily disturbed areas to pre-project conditions
- Implement Best Management Practices
- Implement measures to reduce the spread of invasive species
- Conduct a preconstruction Nesting Migratory Bird and Raptor Survey
- Conduct a preconstruction survey for bats
- Conduct a preconstruction Small Mammal Survey
- Avoid disturbance or harm to wildlife

A National Pollutant Discharge Elimination System permit from the State Water Resources Control Board under Clean Water Act, Section 402 is required.

**6G. Air Quality Conformity**

Air quality conformity is not required.

**6H. Title VI Considerations**

The project complies with Title VI of the Civil Rights Act of 1964 and related statutes. This project will not result in disproportionate adverse transportation impact to minority and low-income populations.

**6I. Noise Abatement Decision Report**

A Noise Abatement Decision Report is not required for this project. Noise levels from concrete pavement removal operations during construction may exceed allowable levels during night-time hours. There are residences located within 100 feet of the eastbound SR 4 to southbound I-5 connector that could possibly be impacted. However, staging at this connector allows removal of the concrete pavement during day-time hours to minimize impacts to residences



from high construction-related noise levels.

## **7. OTHER CONSIDERATIONS AS APPROPRIATE**

### **7A. Transportation Management Plan and Stage Construction**

It is proposed to utilize stage construction and a cross-median detour to reconstruct the mainline pavement. Stage 1 would close the eastbound lanes and utilize the westbound lanes for one traffic lane in each direction, separated by temporary railing (Type K). Similarly, Stage 2 would shift westbound traffic onto the eastbound lanes while the westbound pavement is reconstructed.

For single lane and low volume ramps and connectors, complete closures are proposed for up to 14 days while the pavement is being reconstructed. For connectors from and to westbound SR 4, it is proposed to utilize Navy Drive and the Charter Way/I-5 interchange for a detour. Other local streets would serve as a detour for the local street ramps. The closures would be scheduled to minimize operational impacts.

At a focused constructability meeting on March 7, 2018, stage construction was proposed for high volume, multi-lane connectors by keeping at least one lane open to traffic at all times. After further analysis by the Office of Traffic Management, representatives from Project Management, Traffic Management, Traffic Operations, Maintenance, Construction, and Design met on March 20, 2018 and discussed the proposed staging plans. Due to the anticipated traffic operational issues with extended lane closures, this risk has been added to the Risk Register. To mitigate this risk, the PDT considered other options including replacing the pavement with rapid strength concrete (RSC) which requires shorter cure time and shorter closure period. This option requires up to three full weekend (55 hours) closures at each connector. This strategy and other traffic handling options and pavement rehabilitation strategies will be further evaluated during the design (PS&E) phase.

### **7B. Storm Water**

A Storm Water Data Report (SWDR) has been approved (**Attachment H**) and identified appropriate construction site Best Management Practices (BMPs) to be incorporated during construction. The obliteration and replacement of the existing pavement is considered Redeveloped Area that may require post construction permanent treatment of highway stormwater runoff before reaching Mormon Slough. Possible treatment measures include bioswales and sand traps to be retrofitted into the existing drainage system. Other options will be evaluated during the design phase of the project.

This project will be covered under the Construction General Permit (CGP). The construction contractor will be required to formulate a Storm Water Pollution Prevention Plan (SWPPP) and will be expected to implement construction site

BMPs. The cost for the anticipated temporary construction BMPs are included in the cost estimate.

#### **7C. Complete Streets**

SR 4 within the project limits is not designated as a pedestrian or bicycle facility. Where on- and off-ramps meet local roads, the existing curb ramps meet current Americans with Disability Act standards. There are no feasible improvements within the scope of this project for pedestrian and bicycle accommodation.

#### **7D. Climate Change**

The project is not located within a coastal zone, but due to its relatively close proximity to the San Joaquin River Delta, it could potentially be vulnerable to sea level rise (SLR). The SLR projections are estimated at 14 inches in the year 2050, and a 40 to 55 inch increase in mean sea level by the year 2100. The proposed scope of work is to match the existing profile grade, as raising the profile would in turn require raising 22 structures within the project limits. Due to the low potential for the project to be impacted by an increase in SLR, any substantial additional modification to the project to further reduce or eliminate SLR risk is not cost effective given the 40-year design lifespan of the project.

In an effort to reduce the effect of greenhouse gasses, this project will replace existing lighting with energy-efficient light-emitting diode (LED) lighting, which reduces the associated energy costs by as much as 80 percent.

### **8. FUNDING, PROGRAMMING AND ESTIMATE**

#### Funding

It has been determined that this project is eligible for Federal-aid funding.

#### Programming

The current construction capital cost is \$31,162,000 and the escalated (2019/2020) construction capital cost is \$33,835,000. The escalated construction cost is 10.7% above the programmed amount and will be monitored. The use of RSC to avoid long term lane closures may escalate this cost further. The funding strategy is to process a project change request once the traffic management plan is more refined and the corresponding costs can be determined. The support costs for Construction and PS&E can be managed within G-12 allowances. The current right of way estimate is \$0.

The programmed cost data is shown in the table below.

Fund Source	Fiscal Year Estimate			
	Prior	18/19	19/20	Total
20.XX.201.122				
Component	In thousands of dollars (\$1,000)			
PA&ED Support	538			538
PS&E Support		2,324		2,324
Right-of-Way Support		19		19
Construction Support			4,589	4,589
Right-of-Way			48	48
Construction			30,576	30,576
<b>Total</b>	<b>538</b>	<b>2,343</b>	<b>35,213</b>	<b>38,094</b>

The support cost ratio is 24.67%. Costs at programming were escalated at 4.2% except for R/W which was escalated at 5%.

## 9. DELIVERY SCHEDULE

Project Milestones		Milestone Date (Month/Day/Year)	Milestone Designation (Target/Actual)
PROGRAM PROJECT	M015	08/16/2017	A
BEGIN ENVIRONMENTAL	M020	10/02/2017	A
PA & ED	M200	05/07/2018	T
95% CONSTRUCTABILITY REVIEW	M315	04/01/2019	T
PS&E TO DOE	M377	05/01/2019	T
RIGHT OF WAY CERTIFICATION	M410	10/10/2019	T
READY TO LIST	M460	11/10/2019	T
HEADQUARTERS ADVERTISE	M480	03/02/2020	T
AWARD	M495	05/15/2020	T
APPROVE CONTRACT	M500	07/11/2020	T
CONTRACT ACCEPTANCE	M600	01/05/2021	T
END PROJECT EXPENDITURES	M800	01/05/2023	T
FINAL PROJECT CLOSEOUT	M900	10/31/2024	T

## 10. RISKS

As discussed in the programming section, the traffic management strategy for the ramp closures is a high risk that will impact the construction capital cost. Also, construction contract time will impact the construction support costs. Several other low- and very low-probability risks were identified, mostly in the Environmental and Design categories in the Risk Register. See **Attachment K**.

## 11. EXTERNAL AGENCY COORDINATION

### Federal Highway Administration (FHWA)

This project is considered to be an Assigned Project in accordance with the current Federal Highway Administration (FHWA) and Department of Transportation (Caltrans) Joint Stewardship and Oversight Agreement. This project has not been identified as either a “Project of Division Interest” or “Project of Corporate Interest.”

The project requires a National Pollutant Discharge Elimination System permit from the State Water Resources Control Board under Clean Water Act, Section 402.

### The project requires the following coordination:

General Permits (Regional Permit, Nationwide Permit or Programmatic Permit)

### Regional Water Quality Control Board

Clean Water Act Section 401  
Water Quality Certification

## 12. PROJECT REVIEWS

Scoping team field review	(performed at PSSR stage)	Date	02/04/2016
District Program Advisor	Ali Juma	Date	04/11/2018
Headquarters SHOPP Program Advisor	Ron Jones	Date	
District Maintenance	Long Huynh	Date	04/11/2018
Headquarters Project Delivery Coordinator	Paul Gennaro	Date	
Project Manager	Jes Padda	Date	04/11/2018
FHWA		Date	
District Safety Review		Date	
Constructability Review		Date	03/07/2018
Other		Date	

## 13. PROJECT PERSONNEL

Jes Padda	Project Manager	209-948-7765
Kal Daher	Design Engineer	559-230-3130
Jaycee Azevedo	Environmental Manager	209-941-1919
Toni Welch	Right of Way Manager	209-948-3858

**14. ATTACHMENTS (Number of Pages)**

- A. Location map (1)
- B. Typical Cross Sections (1)
- C. Layout And Stage Construction (1)
- D. Cost Estimate (10)
- E. Categorical Exemption/ Categorical Exclusion (2)
- F. Right of Way Data Sheet (4)
- G. Transportation Management Plan (14)
- H. Storm Water Data Report – Signed Cover Sheet (1)
- I. Pavement Condition Summary Report (1)
- J. 2R Certification (1)
- K. Risk Register (1)

INDEX OF PLANS

SHEET No. DESCRIPTION

STATE OF CALIFORNIA  
 DEPARTMENT OF TRANSPORTATION  
 PROJECT PLANS FOR CONSTRUCTION ON  
**STATE HIGHWAY**  
 IN SAN JOAQUIN COUNTY  
 IN STOCKTON  
 FROM 0.1 MILE EAST OF FRESNO AVENUE  
 TO CENTRAL VIADUCT


TO BE SUPPLEMENTED BY STANDARD PLANS DATED MAY 2015

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
10	SJ	4	R15.5/R16.7		



**BEGIN WORK AND CONSTRUCTION**  
 PM R15.5

**END WORK AND CONSTRUCTION**  
 PM R16.7




PROJECT MANAGER  
 JES PADDA  
 DESIGN ENGINEER  
 KAL DAHER

ATTACHMENT A

PROJECT ENGINEER \_\_\_\_\_ DATE \_\_\_\_\_  
 REGISTERED CIVIL ENGINEER

PLANS APPROVAL DATE \_\_\_\_\_

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



EA	10-1C5000
PROJECT ID	1016000026

NO SCALE



**NOTES:**

1. DIMENSIONS OF THE PAVEMENT STRUCTURES (STRUCTURAL SECTIONS) ARE SUBJECT TO TOLERANCES SPECIFIED IN THE STANDARD SPECIFICATIONS.
2. NEW PAVEMENT TO MATCH EXISTING PAVEMENT CROSS SLOPES AND SUPERELEVATIONS.
3. FOR CRCP RSC LOCATIONS SEE LAYOUT.
4. ALL EXISTING GUARDRAIL TO BE REPLACED WITH MIDWEST GUARDRAIL SYSTEM. SEE LAYOUT FOR LOCATIONS OF EXISTING GUARDRAIL.
5. BRIDGE APPROACH SLABS STRUCTURAL SECTIONS NOT SHOWN.
6. EXISTING OLEANDERS FROM Sta 939+00 TO Sta 969+00 TO REMAIN.
7. EXISTING CONCRETE BARRIER TO BE REMOVED FOR STAGE CONSTRUCTION BETWEEN Sta 978+28 AND Sta 983+50. REMOVED BARRIER TO BE REPLACED IN KIND.
8. LIME TREATMENT OF SUBBASE ASSUMED TO BE REQUIRED.

**ABBREVIATIONS:**

CRCP - CONTINUOUSLY REINFORCED CONCRETE PAVEMENT  
 CRCP RSC - CONTINUOUSLY REINFORCED CONCRETE PAVEMENT RAPID STRENGTH CONCRETE

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
10	SJ	4	R15.5/R16.7		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_

PLANS APPROVAL DATE \_\_\_\_\_

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



**DESIGN DESIGNATION ROUTE 4**

ADT (2016)	18,000	D	57%
ADT (2041)	37,100	T	11.2%
DHV (2061)	61,000	V	70 mph
ESAL	39,326,847	TI <sub>40</sub>	14.0


**PAVEMENT CLIMATE REGION**

INLAND VALLEY


**SUBGRADE TYPE**

TYPE II ( SILTS AND CLAYS )

CONNECTOR/ Ramp	DESCRIPTION	TRAFFIC INDEX (TI)	
		20 Yr (2041)	40 Yr (2061)
A	SB Rte 5 to EB Rte 4	12.5	14.5
B	EB Rte 4 To NB Rte 5	11.0	12.0
C	NB Rte 5 TO WB Rte 4	10.5	12.0
D	WB Rte 4 To SB Rte 5	13.0	14.5
E	SB Rte 5 to WB Rte 4	10.5	12.0
F	EB Rte 4 To SB Rte 5	11.0	12.0
G	NB Rte 5 To EB Rte 4	12.5	14.5
H	WB Rte 4 To NB Rte 5	12.5	14.5
K	Lincoln St On-Ramp	10.0	11.0
L	Lincoln St Off-Ramp	10.0	11.0
M	Center St. On-Ramp	10.5	12.0
N	Center St. Off-Ramp	10.5	12.0



**RAMPS A, D, G AND H**



**ROUTE 4**  
PM R15.5/R16.6

**TYPICAL PAVEMENT STRUCTURAL SECTIONS**

EXISTING	NEW (SOURCE: HDM TABLE 623.1G)
1 0.67' PCC 0.35' CTB 1.98' AS	TI = 14.0 0.85' CRCP OR CRCP RSC 0.25' HMA (TYPE A) 0.70' AS
2 0.20' AC 0.45' AB 1.98' AS	TI = 14.5 0.90' CRCP OR CRCP RSC 0.25' HMA (TYPE A) 0.70' AS
3 0.25' AC 0.55' AB 1.00' (Min) AS	TI = 12.0 0.80' CRCP OR CRCP RSC 0.25' HMA (TYPE A) 0.60' AS
4 0.75' PCC 0.50' CTB 1.75' AS	TI = 11.0 0.90' JPCP 0.25' HMA (TYPE A) 0.60' AS

**TYPICAL CROSS SECTIONS**

**X-1**

NO SCALE

ATTACHMENT B

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION - 06-DESIGN

REVISOR: KAL DAHER

FUNCTIONAL SUPERVISOR: KAL DAHER

DESIGNED BY: \_\_\_\_\_

CHECKED BY: \_\_\_\_\_

REVISOR: \_\_\_\_\_


DATE REVISED: \_\_\_\_\_

DATE PLOTTED => 16-MAY-2018 TIME PLOTTED => 15:34


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
10	SJ	4	R15.5/R16.7		


REGISTERED CIVIL ENGINEER	DATE
PLANS APPROVAL DATE	




THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




RAMPS K AND L




RAMPS E AND F



RAMPS B AND C



RAMP N



RAMP M

TYPICAL CROSS SECTIONS




NO SCALE

X-2

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**Caltrans** 06-DESIGN  
 FUNCTIONAL SUPERVISOR: KAL DAHER  
 REVISIONS: (x) REVISOR: (x) DATE: (x)  
 CALCULATED/DESIGNED BY: (x) CHECKED BY: (x)

10-1C5000  
(1016000026)  
10-SJ-4 PM R15.5/R16.7


**LEGEND:**

-  REPLACE WITH CRCP
-  REPLACE WITH CRCP RSC
-  REPLACE BRIDGE APPROACH SLAB

2016 ADTs SHOWN


**ABBREVIATIONS:**

- CRCP: CONTINUOUS REINFORCED CONCRETE PAVEMENT
- CRCP-RSC: CONTINUOUS REINFORCED CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)



**STAGE CONSTRUCTION**

CONSTRUCT HMA CROSS-MEDIAN DETOUR FROM STA 918+00 TO 926+00 AND FROM 975+00 TO 978+28.  
 REMOVE EXISTING CONCRETE BARRIER FROM STA 978+28 TO STA 983+00.  
 STAGE 1 :SHIFT EB TRAFFIC ACROSS MEDIAN TO WB LANE #1. RECONSTRUCT EB PAVEMENT.  
 STAGE 2 :SHIFT WB TRAFFIC ACROSS MEDIAN TO EB LANE #1. RECONSTRUCT WB PAVEMENT.  
 RAMPS B, C, E & F CLOSE RAMPS FOR 14 DAYS EACH LOCATION. (RAMPS NOT TO BE CLOSED CONCURRENTLY). USE NAVY DRIVE TO I-5/CHARTER WAY I/C FOR DETOUR.  
 RAMP K, L & M CLOSE RAMPS FOR 14 DAYS EACH LOCATION. (RAMPS NOT TO BE CLOSED CONCURRENTLY). USE LOCAL STREETS FOR DETOUR.  
 RAMPS A, D, G, H & N TO BE RECONSTRUCTED WITH CRCP RSC USING 55 HOUR WEEKEND CLOSURES. MULTIPLE WEEKEND CLOSURES WILL BE REQUIRED AT EACH LOCATION.



**LAYOUT AND STAGE CONSTRUCTION**

## Project Report Cost Estimate

**Project ID: 1016000026 (EA 10-1C5000)**

Type of Estimate : Project Report (PR)  
 Program Code : 201.122  
 Project Limits : On Route 4 in Stockton at the Rte 4/Rte 5 Interchange.  
 Description: Pavement Resurfacing and Restoration  
 Scope : Replace pavement with CRCP  
 Alternative : Alternative 1, Programmed Project Alternative

	Current Cost	Escalated Cost
ROADWAY ITEMS	\$ 27,211,700	\$ 29,545,484
STRUCTURE ITEMS	\$ 3,950,000	\$ 4,288,768
<b>SUBTOTAL CONSTRUCTION COST</b>	<b>\$ 31,161,700</b>	<b>\$ 33,834,252</b>
RIGHT OF WAY	\$ -	\$ -
<b>TOTAL CAPITAL OUTLAY COST</b>	<b>\$ 31,162,000</b>	<b>\$ 33,835,000</b>
PR/ED SUPPORT	\$ -	\$ -
PS&E SUPPORT	\$ -	\$ -
RIGHT OF WAY SUPPORT	\$ -	\$ -
CONSTRUCTION SUPPORT	\$ -	\$ -
<b>TOTAL CAPITAL OUTLAY SUPPORT COST*</b>	<b>\$ -</b>	<b>\$ -</b>

<b>TOTAL PROJECT COST</b>
---------------------------

If Project has been programmed enter Programmed Amount \$ -

Date of Estimate (Month/Year) Month / Year  
4 / 2018

Estimated Date of Construction Start (Month/Year) 7 / 2020

Number of Working Days 200 Working Days  
Month / Year

Estimated Mid-Point of Construction (Month/Year) 12 2020

Number of Plant Establishment Days 0 Days

**Estimated Project Schedule**

PID Approval  
 PA/ED Approval 7-May-18  
 PS&E  
 RTL  
 Begin Construction 1-Jul-20

Approved by Project  
 Manager

Jes Padda  
 \_\_\_\_\_  
 Project Manager

\_\_\_\_\_

Date

(209) 948-7765  
 \_\_\_\_\_  
 Phone





**SECTION 1: EARTHWORK**

Item code	Unit	Quantity	Unit Price (\$)	Cost
160101 Clearing & Grubbing	LS	1	x 30,000.00	= \$ 30,000
170101 Develop Water Supply	LS		x	= \$ -
190101 Roadway Excavation (Gores, detour)	CY	5,000	x 20.00	= \$ 100,000
190103 Roadway Excavation (Type Y) ADL	CY		x	= \$ -
190105 Roadway Excavation (Type Z-2) ADL	CY		x	= \$ -
192037 Structure Excavation (Retaining Wall)	CY		x	= \$ -
193013 Structure Backfill (Retaining Wall)	CY		x	= \$ -
193031 Pervious Backfill Material (Retaining Wall)	CY		x	= \$ -
194001 Ditch Excavation	CY		x	= \$ -
198001 Imported Borrow	CY		x	= \$ -
198007 Imported Material (Shoulder Backing)	TON	200	x 100.00	= \$ 20,000
				= \$ -

<b>TOTAL EARTHWORK SECTION ITEMS</b>	<b>\$ 150,000</b>
--------------------------------------	-------------------

**SECTION 2: PAVEMENT STRUCTURAL SECTION**

Item code	Unit	Quantity	Unit Price (\$)	Cost
150771 Remove Asphalt Concrete Dike	LF		x	= \$ -
150860 Remove Base and Surfacing	CY	10,000	x 21.00	= \$ 210,000
153103 Cold Plane Asphalt Concrete Pavement	SQYD		x	= \$ -
1532XX Remove Concrete (pavement, curb and gutter)	CY	60,000	x 30.00	= \$ 1,800,000
250401 Class 4 Aggregate Subbase	CY	33,000	x 30.00	= \$ 990,000
260201 Class 2 Aggregate Base	CY		x	= \$ -
290201 Asphalt Treated Permeable Base	CY		x	= \$ -
365001 Sand Cover	TON		x	= \$ -
374002 Asphaltic Emulsion (Fog Seal Coat)	TON		x	= \$ -
374492 Asphaltic Emulsion (Polymer Modified)	TON		x	= \$ -
3750XX Screenings (Type XX)	TON		x	= \$ -
377501 Slurry Seal	TON		x	= \$ -
390095 Replace Asphalt Concrete Surfacing	CY		x	= \$ -
390132 Hot Mix Asphalt (Type A)	TON	20,000	x 90.00	= \$ 1,800,000
390136 Temp HMA (shld widening, X-median detour)	TON	5,000	x 90.00	= \$ 450,000
390137 Rubberized Hot Mix Asphalt (Gap Graded)	TON		x	= \$ -
393003 Geosynthetic Pavement Interlayer	SQYD		x	= \$ -
39405X Shoulder Rumber Strip (HMA, Type XX Inden	STA		x	= \$ -
394071 Place Hot Mix Asphalt Dike	LF	10,000	x 3.00	= \$ 30,000
394090 Place Hot Mix Asphalt (Misc. Area)	SQYD	2,000	x 5.00	= \$ 10,000
397005 Tack Coat	TON	50	x 150.00	= \$ 7,500
401000 Concrete Pavement (CRCP)	CY	21,000	x 250.00	= \$ 5,250,000
401108 Replace Concrete Pavement (Rapid Strength	CY	11,700	x 350.00	= \$ 4,095,000
400092 Expansion Joint (Type WF)	LF	2,400	x 50.00	= \$ 120,000
400065 Terminal Joint (Type E)	LF	2,400	x 30.00	= \$ 72,000
Wide falng Beam	LF	45	x 200.00	= \$ 9,000
413112A Repair Spalled Joints (Polyester Grout)	SQYD		x	= \$ -
413115 Seal Existing Concrete Pavement Joint	LF		x	= \$ -
420102 Groove Existing Concrete Pavement	SQYD		x	= \$ -
420201 Grind Existing Concrete Pavement	SQYD		x	= \$ -
Minor Concrete (Misc. Const, Conc CURB)	CY	500	0 200.00	= \$ 100,000
731530 Minor Concrete (Textured Paving)	CY	400	x 500.00	= \$ 200,000
			x	= \$ -

<b>TOTAL STRUCTURAL SECTION ITEMS</b>	<b>\$ 15,143,500</b>
---------------------------------------	----------------------



**SECTION 3: DRAINAGE**

Item code	Unit	Quantity	Unit Price (\$)	Cost
150206 Abandon Culvert	LF	x	= \$	-
150805 Remove Drairage Facility	LS	1	x 15,000.00 = \$	15,000
150820 Modify Inlet	EA	x	= \$	-
152430 Adjust Inlet	LF	x	= \$	-
155003 Cap Inlet	EA	x	= \$	-
193114 Sand Backfill	CY	x	= \$	-
510502 Minor Concrete (Minor Structure)	CY	80	x 2,000.00 = \$	160,000
510512 Minor Concrete (Box Culvert)	CY	x	= \$	-
62XXXX XXX" APC Pipe	LF	x	= \$	-
64XXXX XXX" Plastic Pipe	LF	x	= \$	-
65XXXX 24" RCP Pipe	LF	300	x 250.00 = \$	75,000
66XXXX 24" CSP Pipe	LF	450	x 200.00 = \$	90,000
68XXXX Edge Drain	LF	2,000	x 25.00 = \$	50,000
69XXXX XXX" Pipe Downdrain	LF	x	= \$	-
70XXXX XXX" Pipe Inlet	LF	x	= \$	-
70XXXX XXX" Pipe Riser	LF	x	= \$	-
70XXXX XXX" Flared End Section	EA	4	x 800.00 = \$	3,200
703233 Grated Line Drain	LF	x	= \$	-
72XXXX Rock Slope Protection (Type and Method)	CY	300	x 300.00 = \$	90,000
721420 Concrete (Ditch Lining)	CY	x	= \$	-
721430 Concrete (Channel Lining)	CY	x	= \$	-
729010 Rock Slope Protection Fabric	SQYD	500	x 12.00 = \$	6,000
750001 Miscellaneous Iron and Steel temp drainage	LB	1,500	x 3.00 = \$	4,500
	LS	1	x 10,000.00 = \$	10,000
	x		= \$	-
	x		= \$	-
<b>TOTAL DRAINAGE ITEMS</b>				<b>\$ 503,700</b>

**SECTION 4: SPECIALTY ITEMS**

Item code	Unit	Quantity	Unit Price (\$)	Cost
070012 Progress Schedule (Critical Path Method)	LS	1	x 5,000.00 = \$	5,000
150662 Remove Metal Beam Guard Railing	LF	7,000	x 15.00 = \$	105,000
150668 Remove Terminal Systems	EA	x	= \$	-
1532XX Remove Barrier (Concrete)	LF	500	x 40.00 = \$	20,000
153250 Remove Sound Wall	SQFT	x	= \$	-
190110 Lead Compliance Plan	LS	1	x 2,000.00 = \$	2,000
49XXXX CIDH Concrete Piling ( <i>Insert Diameter</i> )	LF	x	= \$	-
510060 Structural Concrete (Retaining Wall)	CY	x	= \$	-
510133 Class 2 Concrete (Retaining Wall)	CY	x	= \$	-
510524 Minor Concrete (Sound Wall)	CY	x	= \$	-
5110XX Architectural Treatment ( <i>Insert Type</i> )	SQFT	x	= \$	-
511048 Apply Anti-Graffiti Coating	SQFT	x	= \$	-
5136XX Reinforced Concrete Crib Wall ( <i>Insert Type</i> )	SQFT	x	= \$	-
518002 Sound Wall (Masonry Block)	SQFT	x	= \$	-
520103 Bar Reinf. Steel (Retaining Wall)	LB	x	= \$	-
80XXXX Fence ( <i>Insert Type</i> )	LF	x	= \$	-
832001 Metal Beam Guard Railing	LF	7,000	x 30.00 = \$	210,000
839310 Double Thrie Beam Barrier	LF	x	= \$	-
839521 Cable Railing	LF	x	= \$	-
83954X Transition Railing ( <i>Insert Type</i> )	EA	20	x 4,000.00 = \$	80,000
8395XX Terminal System (Type CAT)	EA	x	= \$	-
8395XX Alternative Flared Terminal System	EA	20	x 3,000.00 = \$	60,000
8395XX End Anchor Assembly ( <i>Insert Type</i> )	EA	x	= \$	-
839561 Rail Tensioning Assembly	EA	x	= \$	-
839XXX Crash Cushion ( <i>Insert Type</i> )	EA	x	= \$	-
83XXXX Concrete Barrier ( <i>Concrete</i> )	LF	500	x 80.00 = \$	40,000
			= \$	-
<b>TOTAL SPECIALTY ITEMS</b>				<b>\$ 522,000</b>

**SECTION 5: ENVIRONMENTAL**

**5A - ENVIRONMENTAL MITIGATION**

Item code	Unit	Quantity	Unit Price (\$)	Cost
Biological Mitigation	LS	x	= \$	-
071325 TEMPORARY REINFORCED SILT FENCE	LF	x	= \$	-
071325 Temporary Fence (Type ESA)	LF		= \$	-
	LS		= \$	-
<b>Subtotal Environmental</b>				<b>\$ -</b>

**5B - LANDSCAPE AND IRRIGATION**

Item code	Unit	Quantity	Unit Price (\$)	Cost
200001 Highway Planting	LS	x	= \$	-
20XXXX XXX" (Insert Type) Conduit (Use for	LF	x	= \$	-
20XXXX Extend XXX" (Insert Type) Conduit	LF	x	= \$	-
201700 Imported Topsoil	CY	x	= \$	-
2030XX Erosion Control (Type __)	Acre	6	x 15,000.00 = \$	90,000
203021 Fiber Rolls	LF	x	= \$	-
203026 Move In/ Move Out (Erosion Control)	EA	x	= \$	-
204099 Plant Establishment Work	LS	x	= \$	-
204101 Extend Plant Establishment (X Years)	LS	x	= \$	-
208000 Irrigation System	LS	x	= \$	-
208304 Water Meter	EA	x	= \$	-
209801 Maintenance Vehicle Pullout	EA	8	x 15,000.00 = \$	120,000
<b>Subtotal Landscape and Irrigation</b>				<b>\$ 210,000</b>

**5C - NPDES**

Item code	Unit	Quantity	Unit Price (\$)	Cost
074016 Construction Site Management	LS	1	x 70,000.00 = \$	70,000
074017 Prepare WPCP	LS	1	x 6,000.00 = \$	6,000
074019 Prepare SWPPP	LS	x	= \$	-
074023 Temporary Erosion Control	Acre	3	x 10,000.00 = \$	30,000
074027 Temporary Erosion Control Blanket	SQYD	x	= \$	-
074028 Temporary Fiber Roll	LF	7,000	x 3.50 = \$	24,500
074032 Temporary Concrete Washout Facility	EA	x	= \$	-
074033 Temporary Construction Entrance	EA	12	x 2,500.00 = \$	30,000
074035 Temporary Check Dam	LF	x	= \$	-
074037 Move In/ Move Out (Temporary Erosion Con	EA	x	= \$	-
074038 Temp. Drainage Inlet Protection	EA	30	x 350.00 = \$	10,500
074041 Street Sweeping	LS	1	x 10,000.00 = \$	10,000
074042 Temporary Concrete Washout (Portable)	LS	1	x 35,000.00 = \$	35,000
Permanenet Treatment BMPs	LS	1	x 250,000.00 = \$	250,000

**Supplemental Work for NPDES**

(These costs are not accounted in total here but under Supplemental Work on sheet 7 of 11).

066595 Water Pollution Control Maintenance Sharing	LS	1	x 10,000.00 = \$	10,000
066596 Additional Water Pollution Control**	LS	1	x 25,000.00 = \$	25,000
066597 Storm Water Sampling and Analysis***	LS	1	x 5,000.00 = \$	5,000

**Subtotal NPDES (Without Supplemental Work) \$ 466,000**

\*Applies to all SWPPPs and those WPCPs with sediment control or soil stabilization BMPs.

\*\*Applies to both SWPPPs and WPCP projects.

\*\*\* Applies only to project with SWPPPs.

<b>TOTAL ENVIRONMENTAL</b>	<b>\$ 676,000</b>
----------------------------	-------------------

**SECTION 6: TRAFFIC ITEMS**

**6A - Traffic Electrical**

Item code	Unit	Quantity	Unit Price (\$)	Cost
150760 Remove Sign Structure	EA	x	= \$	-
151581 Reconstruct Sign Structure	EA	x	= \$	-
152641 Modify Sign Structure	EA	x	= \$	-
5602XX Furnish Sign Structure	LB	x	= \$	-
5602XX Install Sign Structure	LB	x	= \$	-
56XXXX XXX" CIDHC Pile (Sign Foundation)	LF	x	= \$	-
860090 Maintain Existing Traffic Management	LS	x	= \$	-
860810 Inductive Loop Detectors	EA	x	= \$	-
86055X Lighting & Sign Illumination	LS	x	= \$	-
8607XX Interconnection Facilities	LS	x	= \$	-
8609XX Traffic Monitoring Stations	LS	1 x	200,000.00 = \$	200,000
860XXX Upgrade Lighting	LS	1 x	442,000.00 = \$	442,000
8611XX Ramp Metering System (Location X)	LS	x	= \$	-
8611XX Ramp Metering System (Location X)	LS	x	= \$	-
86XXXX Fiber Optic Conduit System	LS	x	= \$	-
XXXXX Upgrade Service Equipmet (To Type III)	EA	4 x	18,500.00 = \$	74,000
<i>Subtotal Traffic Electrical</i>				<b>\$ 716,000</b>

**6B - Traffic Signing and Striping**

Item code	Unit	Quantity	Unit Price (\$)	Cost
120090 Construction Area Signs	LS	1 x	25,000.00 = \$	25,000
150701 Remove Yellow Painted Traffic Stripe	LF	x	= \$	-
150710 Remove Traffic Stripe	LF	x	= \$	-
150713 Remove Pavement Marking	SQFT	x	= \$	-
820250 Remove Roadside Sign	EA	x	= \$	-
820530 Reset Roadside Sign	EA	20 x	300.00 = \$	6,000
152390 Relocate Roadside Sign	EA	x	= \$	-
820840 Roadside Sign (One Post)	EA	x	= \$	-
820850 Roadside Sign (Two Post)	EA	x	= \$	-
820XXX Furnish Sign Panels	SQFT	4,000 x	25.00 = \$	100,000
560XXX Install Sign Panels	SQFT	4,000 x	5.00 = \$	20,000
82010X Pavment marker	LS	1 x	20,000.00 = \$	20,000
84XXXX Pavement Delineation	LS	1 x	120,000.00 = \$	120,000
<i>Subtotal Traffic Signing and Striping</i>				<b>\$ 291,000</b>

**6C - Stage Construction and Traffic Handling**

Item code	Unit	Quantity	Unit Price (\$)	Cost
120100 Traffic Control System	LS	1 x	250,000.00 = \$	250,000
120120 Type III Barricade	EA	650 x	15.00 = \$	9,750
120143 Temporary Pavement Delineation	LS	1 x	30,000.00 = \$	30,000
12016X Channelizer	EA	5,000 x	10.00 = \$	50,000
128650 Portable Changeable Message Signs	LS	1 x	70,000.00 = \$	70,000
129000 Temporary Railing (Type K)	LF	32,000 x	12.00 = \$	384,000
129100 Temp. Crash Cushion Module	EA	200 x	200.00 = \$	40,000
129099A Traffic Plastic Drum	EA	x	= \$	-
Temporary Crash Cushion	EA	12 x	10,000.00 = \$	120,000
Traffic Handling signs	LS	1 x	50,000.00 = \$	50,000
<i>Subtotal Stage Construction and Traffic Handling</i>				<b>\$ 1,003,750</b>

<b>TOTAL TRAFFIC ITEMS</b>	<b>\$ 2,010,800</b>
----------------------------	---------------------

**SECTION 7: DETOURS**

Include constructing, maintaining, and removal

Item code	Unit	Quantity	Unit Price (\$)	Cost
0713XX Temporary Fence (Type X)	LF	x	= \$	-
07XXXX Temporary Drainage	LS	x	= \$	-
120143 Temporary Pavement Delineation	LS	x	= \$	-
1286XX Temporary Signals	LS	x	= \$	-
129000 Temporary Railing (Type K)	LF	x	= \$	-
190101 Roadway Excavation	CY	x	= \$	-
198001 Imported Borrow	CY	x	= \$	-
198050 Embankment	CY	x	= \$	-
250401 Class 4 Aggregate Subbase	CY	x	= \$	-
260201 Class 2 Aggregate Base	CY	x	= \$	-
390132 Hot Mix Asphalt (Type A)	TON	x	= \$	-
	LS	x	= \$	-
<b>TOTAL DETOURS</b>				<b>\$ -</b>

SUBTOTAL SECTIONS 1-7 \$ 19,006,000

**SECTION 8: MINOR ITEMS**

**8A - Americans with Disabilities Act Items**

ADA Items 0.0% \$ -

**8B - Bike Path Items**

Bike Path Items 0.0% \$ -

**8C - Other Minor Items**

Other Minor Items 1.0% \$ 190,060

Total of Section 1-7 \$ 19,006,000 x 1.0% = \$ 190,060

**TOTAL MINOR ITEMS \$ 190,100**

**SECTIONS 9: MOBILIZATION**

Item code	Quantity	Unit Price (\$)	Cost
999990 Total Section 1-8	19,196,100	x 8%	= \$ 1,439,708
<b>TOTAL MOBILIZATION</b>			<b>\$ 1,439,800</b>

**SECTION 10: SUPPLEMENTAL WORK**

Item code	Unit	Quantity	Unit Price (\$)	Cost
066015 Federal Trainee Program	LS	1	x 13,600.00	= \$ 13,600
066063 Traffic Management Plan - Public Informatic	LS	1	x 30,000.00	= \$ 30,000
066090 Maintain Traffic	LS	1	x 100,000.00	= \$ 100,000
066094 Value Analysis	LS	1	x 10,000.00	= \$ 10,000
066204 Remove Rock & Debris	LS		x	= \$ -
066222 Locate Existing Cross-Over	LS		x	= \$ -
066670 Payment Adjustments For Price Index Fluct	LS	1	x 70,000.00	= \$ 70,000
066700 Partnering	LS	1	x 35,000.00	= \$ 35,000
066866 Operation of Existing Traffic Management S	LS		x	= \$ -
066920 Dispute Review Board	LS	1	x 7,500.00	= \$ 7,500
Lime Treatment of Subbase	LS	1	x 300,000.00	= \$ 300,000
<i>Cost of NPDES Supplemental Work specified in Section 5C</i>				<i>= \$ 40,000</i>
Total Section 1-8		\$ 19,196,100	0%	= \$ -
<b>TOTAL SUPPLEMENTAL WORK</b>			<b>\$ 606,100</b>	

**SECTION 11: STATE FURNISHED MATERIALS AND EXPENSES**

Item code	Unit	Quantity	Unit Price (\$)	Cost
066063 Public Information	LS		x	= \$0
066105 RE Office	LS	1	x 200,000.00	= \$200,000
066803 Padlocks	LS		x	= \$0
066838 Reflective Numbers and Edge Sealer	LS		x	= \$0
066901 Water Expenses	LS		x	= \$0
066062A COZEEP Expenses	LS	1	x 600,000	= \$600,000
06684X Ramp Meter Controller Assembly	LS		x	= \$0
06684X TMS Controller Assembly	LS		x	= \$0
06684X Traffic Signal Controller Assembly	LS		x	= \$0

Total Section 1-8                           \$   19,196,100                   0%       = \$       -

<b>TOTAL STATE FURNISHED</b>	<b>\$800,000</b>
------------------------------	------------------

**SECTION 12: TIME-RELATED OVERHEAD**

Estimated Time-Related Overhead (TRO) Percentage (0% to 10%) = 7%

Item code	Unit	Quantity	Unit Price (\$)	Cost
				Total Project Cost   \$   25,992,000   (used to check if proj
070018 Time-Related Overhead	WD	200	X	= \$1,620,300

<b>TOTAL TIME-RELATED OVERHEAD</b>	<b>\$1,620,300</b>
------------------------------------	--------------------

**SECTION 13: CONTINGENCY**

(Pre-PSR 30%-50%, PSR 25%, Draft PR 20%, PR 15%, after PR approval 10%, Final PS&E 5%)

Total Section 1-11                           \$   23,662,300       x   15%       = \$3,549,345

<b>TOTAL CONTINGENCY</b>	<b>\$3,549,400</b>
--------------------------	--------------------

**II. STRUCTURE ITEMS**

	<u>Approach Slabs</u>	<u>Aggregate Base</u>	<u>Joint Seals</u>
DATE OF ESTIMATE	04/11/18	04/11/18	04/11/18
Bridge Name	various	various	
Bridge Number			
Structure Type			
Structural concrete	3000 CY	1000.00 CY	
Total Bridge Length (Feet)			
Total Area (Square Feet)			
Structure Depth (Feet)			
Footing Type (pile or spread)			
Cost Per CY	\$1,100.00	\$50.00	

<b>COST OF EACH STRUCTURE</b>	<b>\$3,300,000.00</b>	<b>\$50,000.00</b>	<b>\$600,000.00</b>
-------------------------------	-----------------------	--------------------	---------------------

DATE OF ESTIMATE	00/00/00	00/00/00	00/00/00
Name	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Bridge Number	57-XXX	57-XXX	57-XXX
Structure Type	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Width (Feet) [out to out]	0.00 LF	0.00 LF	0.00 LF
Total Length (Feet)	0.00 LF	0.00 LF	0.00 LF
Total Area (Square Feet)	0 SQFT	0.00 SQFT	0.0 SQFT
Structure Depth (Feet)	0.00 LF	0.00 LF	0.00 LF
Footing Type (pile or spread)	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Cost Per Square Foot	\$0.00	\$0.00	\$0.00

<b>COST OF EACH STRUCTURE</b>	<b>\$0.00</b>	<b>\$0.00</b>	<b>\$0.00</b>
-------------------------------	---------------	---------------	---------------

<b>TOTAL COST OF BRIDGES</b>	<b>\$3,950,000.00</b>
------------------------------	-----------------------

<b>TOTAL COST OF BUILDINGS</b>	<b>\$0.00</b>
--------------------------------	---------------

<b>TOTAL COST OF STRUCTURES<sup>1</sup></b>	<b>\$3,950,000.00</b>
---	-----------------------

Estimate Prepared By: \_\_\_\_\_  
XXXXXXXXXXXXXXXXXXXX ----- Division of Structures

\_\_\_\_\_ Date

<sup>1</sup>Structure's Estimate includes Overhead and Mobilization.  
Add more sheets if needed. Call them 9a, 9b, 9c, ..., etc



### III. RIGHT OF WAY

Fill in all of the available information from the Right of Way data sheet.

A)	A1) Acquisition, including Excess Land Purchases, Damages & Goodwill,		\$	0
	A2) SB-1210		\$	0
B)	Acquisition of Offsite Mitigation		\$	0
C)	C1) Utility Relocation (State Share)		\$	0
	C2) Potholing (Design Phase)		\$	0
D)	Railroad Acquisition		\$	0
E)	Clearance / Demolition		\$	0
F)	Relocation Assistance (RAP and/or Last Resort Housing Costs)		\$	0
G)	Title and Escrow		\$	0
H)	Environmental Review		\$	0
I)	Condemnation Settlements	0%	\$	0
	(Items G & H applied to items A + B)			
J)	Design Appreciation Factor	0%	\$	0
K)	Utility Relocation (Construction Cost)		\$	0

L)

<b>TOTAL RIGHT OF WAY ESTIMATE</b>	<b>\$0</b>
------------------------------------	------------

(Excluding Item #8 - Hazardous Waste)

M)

<b>TOTAL R/W ESTIMATE: Escalated</b>	<b>\$0</b>
--------------------------------------	------------

N)

<b>Right of Way Support</b>	<b>\$</b>	<b>0</b>
-----------------------------	-----------	----------

Support Cost  
Estimate Prepared  
By

Project Coordinator<sup>1</sup>

Phone

Utility Estimate  
Prepared By

Utility Coordinator<sup>2</sup>

Phone

R/W Acquisition  
Estimate Prepared  
By

Right of Way Estimator<sup>3</sup>

Phone

<sup>1</sup> When estimate has Support Costs only

**CATEGORICAL EXEMPTION/CATEGORICAL EXCLUSION DETERMINATION FORM**

<b>10-SJ-4</b>	<b>15.5/16.7</b>	<b>10-1C500</b>	<b>10-1600-0026</b>
Dist.-Co.-Rte. (or Local Agency)	P.M./P.M.	E.A/Project No.	Federal-Aid Project No. (Local Project)/Project No.

**PROJECT DESCRIPTION:** (Briefly describe project including need, purpose, location, limits, right-of-way requirements, and activities involved in this box. Use Continuation Sheet, if necessary.)

California Department of Transportation (Caltrans) proposes a resurfacing and restoration roadway rehabilitation project on State Route (SR) 4 at the Route 4 / I-5 interchange in the city of Stockton, San Joaquin County. The purpose of this project is to rehabilitate the roadway, prevent costly roadway repairs, improve ride quality and extend pavement service life. The project is needed to address continued pavement deterioration on SR 4 and its connectors with Interstate 5. All work for this federally funded project would take place within existing Caltrans right of way.

**CEQA COMPLIANCE** (for State Projects only)

Based on an examination of this proposal and supporting information, the following statements are true and exceptions do not apply (See 14 CCR 15300 et seq.):

- If this project falls within exempt class 3, 4, 5, 6 or 11, it does not impact an environmental resource of hazardous or critical concern where designated, precisely mapped, and officially adopted pursuant to law.
- There will not be a significant cumulative effect by this project and successive projects of the same type in the same place, over time.
- There is not a reasonable possibility that the project will have a significant effect on the environment due to unusual circumstances.
- This project does not damage a scenic resource within an officially designated state scenic highway.
- This project is not located on a site included on any list compiled pursuant to Govt. Code § 65962.5 ("Cortese List").
- This project does not cause a substantial adverse change in the significance of a historical resource.

**CALTRANS CEQA DETERMINATION** (Check one)

- Not Applicable – Caltrans is not the CEQA Lead Agency       Not Applicable – Caltrans has prepared an Initial Study or Environmental Impact Report under CEQA
- Exempt by Statute. (PRC 21080[b]; 14 CCR 15260 et seq.)  
Based on an examination of this proposal, supporting information, and the above statements, the project is:
- Categorically Exempt. Class 1.** (PRC 21084; 14 CCR 15300 et seq.)
- Categorically Exempt. General Rule exemption.** [This project does not fall within an exempt class, but it can be seen with certainty that there is no possibility that the activity may have a significant effect on the environment (CCR 15061[b][3].)]

**Jaycee Azevedo**

Print Name: Senior Environmental Planner or Environmental Branch Chief

  
Signature

  
Date

**Jes Padda**

Print Name: Project Manager

  
Signature

  
Date

**NEPA COMPLIANCE**

In accordance with 23 CFR 771.117, and based on an examination of this proposal and supporting information, the State has determined that this project:

- does not individually or cumulatively have a significant impact on the environment as defined by NEPA, and is excluded from the requirements to prepare an Environmental Assessment (EA) or Environmental Impact Statement (EIS), and
- has considered unusual circumstances pursuant to 23 CFR 771.117(b).

**CALTRANS NEPA DETERMINATION** (Check one)

- 23 USC 326:** The State has determined that this project has no significant impacts on the environment as defined by NEPA, and that there are no unusual circumstances as described in 23 CFR 771.117(b). As such, the project is categorically excluded from the requirements to prepare an EA or EIS under the National Environmental Policy Act. The State has been assigned, and hereby certifies that it has carried out the responsibility to make this determination pursuant to Chapter 3 of Title 23, United States Code, Section 326 and a Memorandum of Understanding dated May 31, 2016, executed between the FHWA and the State. The State has determined that the project is a Categorical Exclusion under:
- 23 CFR 771.117(c): activity (c)(26)**
- 23 CFR 771.117(d): activity (d)( )**
- Activity \_\_\_ listed in Appendix A of the MOU between FHWA and the State**
- 23 USC 327:** Based on an examination of this proposal and supporting information, the State has determined that the project is a Categorical Exclusion under 23 USC 327. The environmental review, consultation, and any other actions required by applicable Federal environmental laws for this project are being, or have been, carried out by Caltrans pursuant to 23 USC 327 and the Memorandum of Understanding dated December 23, 2016 and executed by FHWA and Caltrans.

**Jaycee Azevedo**


Print Name: Senior Environmental Planner or Environmental Branch Chief

  
Signature

  
Date

**Jes Padda**

Print Name: Project Manager/DLA Engineer

  
Signature

  
Date

Date of Categorical Exclusion Checklist completion: 2/10/18

Date of ECR or equivalent : 1/4/18

Briefly list environmental commitments on continuation sheet. Reference additional information, as appropriate (e.g., CE checklist, additional studies and design conditions).

**CATEGORICAL EXEMPTION/CATEGORICAL EXCLUSION DETERMINATION FORM**

**Continuation Sheet**

<b>10-SJ-4</b>	<b>15.5/16.7</b>	<b>10-1C500</b>	<b>10-1600-0026</b>
Dist.-Co.-Rte. (or Local Agency)	P.M./P.M.	E.A/Project No.	Federal-Aid Project No. (Local Project)/Project No.

Continued from page 1:

**A. General:**

**Revalidation**

Under the California Environmental Quality Act (CEQA), this project is Categorical Exempt and under the National Environmental Policy Act (NEPA) it is Categorical Excluded unless:

- 1) the scope of the project changes to include additional activities or areas;
- 2) there is unforeseen discovery of sensitive or cultural resources.

**B. Air/Noise/Water:**

Project will not affect air quality or water quality and no further investigation is recommended. Project noise impacts are expected to be within limits except for temporary construction impacts. Caltrans Standard Specifications Section will be in the contract.

**C. Cultural:**

The project has no potential to affect historic properties eligible for or listed in the National Register of Historic Places.

**D. Biology:**

In accordance to the Migratory Bird Treaty Act (MBTA), a Bird Protection Special Provision shall be included in the construction contract. If construction occurs during the nesting season (February 15 to September 1), a preconstruction survey for migratory birds and raptors will be required fourteen (14) days prior to construction. A 100 foot (ft) buffer shall be established around migratory bird active nests until the young have fledged. If it is a raptor then a 300 ft. buffer will need to be maintained until the young have fledged. For the Swainson's hawk, a 600-foot ESA buffer is required.

If an active Burrowing Owl is observed during pre-construction surveys, a no work buffer will be established. If construction occurs between April 1 and October 15, the buffer is 565 ft. around the active burrow. If construction occurs between October 16 and March 31, a 165 ft. no work buffer is required.

**E. Hazardous Waste:**

The Caltrans Standard Special Provision pertaining to earth material containing Lead, 7-1.02K(6)(j)(iii), shall be added to the construction contract. Replacing guardrail post would require disposal of Treated Wood Waste and the Caltrans Standard Special Provision, 14-11.14, shall be added to the construction contract.

**F. 4F Evaluation:**

The project area does not contain any 4F resources.

## Memorandum

To: JES PADDA

Date: 3/20/2018

Attn: KAL DAHER

File: CD 10 EA 1C500

Alt NA-REV1

Co SJ RTE 4

## DESCRIPTION:

PAVEMENT RESURFACING AND PRESERVATION

From: Department of Transportation  
Division of Right of Way Central Region

Subject: RIGHT OF WAY DATA SHEET

We have completed an estimate of the right of way costs for the above-referenced project based on the Right of Way Data Sheet Request Form dated 3/5/2018

The following assumptions and limiting conditions were identified:

## Parcel


The Data Sheet request indicates that all work on this project will occur within the State's right of way, with no additional right of way needed for this project.

## Utility

Project engineer states on the Right of Way data sheet request form that no potholing or utility relocation/involvement will be necessary. It is assumed that this means all utility facilities above ground and underground in the project area will be worked around. Any adjustment of facilities constitutes involvement and the full R/W utility process and timeline would be necessary before the project could be certified.

Right of Way Lead Time will require a minimum of 2 months after we receive Certified Appraisal Maps and/or Utility Conflict Plans, obtained necessary environmental clearance and applicable freeway agreements have been approved.

Recommended for approval by:

  
TONI WELCH  
Senior Right of Way Agent  
(209)948-3858



Right Of Way Cost Estimate	Current Year 2018	Contingency Rate	Right of Way Escalation Rate	Escalated Year 2019
Acquisition:	\$0	2%	5%	\$0
Mitigation:	\$0	2%	5%	\$0
State Share of Utilities:	\$0	25%	5%	\$0
Expert Witness:	\$0	2%	5%	\$0
Relocation Assistance:	\$0	2%	5%	\$0
Demolition and Clearance:	\$0	2%	5%	\$0
Title and Escrow:	\$0	2%	5%	\$0
Ad Signs:	\$0	2%	5%	\$0
<b>Total Current Value:</b> If RW Cost Est fields are blank, Costs = \$0	\$0			\$0

NOTE: above estimate includes railroad engineering in the amount of: \$0.00

Estimated Construction Contract Work (CCW):

R/W LEAD TIME/Mo. 2

Cost Break Down	
Pot Hole	
Mitigation	
Land Bank	
Permit Fees	

Parcel Area	
Total R/W Required:	
Total Excess Area:	

Misc R/W Work	
# of RAP Displacements:	0
# of Clearance/Demos:	
# of Const Permits:	
# of Condemnations:	

Utilities	
<input type="checkbox"/> Companies to be potholed	
<input type="checkbox"/> Companies for Verification	
<input type="checkbox"/> Companies for Utility Relocations	
JUA/CCUAs are not needed	

Parcel Data		
# of Parcel Type X:		
# of Parcel Type A: less than \$10,000 non-complex		
# of Parcel Type B: more than \$10,000 non-complex		
# of Parcel Type C: complex, special valuation		
# of Parcel Type D: most complex and time consuming		# of Duals Needed:
<b>Totals:</b>	0	<b>Totals:</b> 0

# of Excess Parcels:

RR Involvement	
Railroad Facilities or Right of Way Affected?	Yes
Const/Maint Agreement:	No
Service Contract Count:	0
Right of Entry:	No
Clauses:	Yes
Estimated Lead-time	2 months

**General Description of Railroad Involvement:**

This project does not include work on the railroad property, but a railroad track is shown on the general plan sheet within the vicinity of the project limits. Do not trespass on railroad property within or near the project limits. A Clearance memo with clauses will be required.

General Description of R/W and Excess Lands Required (zoning, use, major improvements, critical or sensitive parcels, etc.):

The Data Sheet request indicates that all work on this project will occur within the State's right of way, with no additional right of way needed.

General Description of Utility Involvement:

IN STOCKTON FROM 0.1 MILES EAST OF FRESNO AVE TO CENTRAL VIADUCT - PAVEMENT RESURFACING AND PRESERVATION. Project engineer states on the data sheet request form that no potholing or utility relocation/involvement will be necessary.

Is there a significant effect on assessed valuation:

No

Were any previously unidentified sites with hazardous waste or material found:

No

Are RAP displacements required:

No

# of single family:

# of multi-family:

# of business/nonprofit:

# of farms:

Sufficient replacement housing will be available without last resort housing:

Are material borrow or disposal sites required:

No

Are there potential relinquishments or abandonments:

No

Are there any existing or potential airspace sites:

No

Are environmental mitigation parcels required:

No

Data for evaluation provided by:

Estimator:

JAMES SUMMERTON

3/5/2018

Railroad Liaison Agent:

Gina Pippenger

3/19/2018

Utility Relocation Coordinator:

JAMES SUMMERTON

3/5/2018

I have personally reviewed this Right of Way Sheet and all supporting information. I find this Data Sheet complete and current, subject to the limiting conditions set forth.

Date

ENTERED PMCS

3/20/2018

BY: JAMES SUMMERTON

JAMES GONZALEZ

Office Chief, Central Region Right of Way



## Environmental Division Mitigation and Compliance Cost Estimate (MCCE)

This MCCE is for: **FED**

Oversight Project:

Dist - Co - Rte - PM: 10-SJ-VAR-15,500/16.500

EA (Proj ID): 10-1C500\_ (1016000026)

Project Name: SJ SR 4 Pavement Resurfacing and Restoration

Alternative #: \_\_\_\_\_

Project Manager: PADDA, JESKRN S

Phone Number: 909-917-8839

MCCE Prepared By: Zorayda Lao

Date: \_\_\_\_\_

Phone Number: 209-948-7879

	232/332 Dollars	FY	Acres/Credits	ROW \$ Planned	FY	ROW \$ Actual	Permit	Construction 042\$(BEEs)	FY
Other									
NOI/NOT							<input type="checkbox"/>	\$606	20/21
Permit Fees									
CDFW Document Filing Fee				\$0			<input type="checkbox"/>		
<b>TOTAL</b>				\$0				\$606	

Comments (explanation and risk management plan attached)

Approved By:

*Zorayda Lao*  
Environmental Branch Chief

Date:

1/31/18

If Right of Way Capital (050) is needed:

*[Signature]*  
Right-of-Way Office Chief, Mitigation

Date:

3/20/18

If cultural and biology mitigation totals more than \$500,000:

\_\_\_\_\_  
Environmental Office Chief

Date: \_\_\_\_\_

Submitted to PM on: 2/23

Initial \_\_\_\_\_

### D-10 TRANSPORTATION MANAGEMENT PLAN CHECKLIST

District - Project No: 1016000026      EA: 1C500  
 Date Prepared: March 22, 2018  
 Prepared By: Julio Hernandez  
 Requested By: Kal Daher

Co.-Rte.-P.M. 10-SJ-4-R15.5/R16.7  
 Location: 0.1 MI E OF FRESNO ST TO CENTRAL VIADUCT

Stage of Project (X box)       PID     PSR     PR     PS&E XX%    Description: PAVEMENT REPLACEMENT

Date Signed
 Date Signed
 Date Signed
 Date Signed

REQUIRED	RECOMMENDED	NOT APPLICABLE	BEES Item No	COMMENTS	ITEM COST	REQUIRED IN SPEC.
----------	-------------	----------------	--------------	----------	-----------	-------------------

**1.0 Public Information Strategies**

- 1.1 Brochures and Mailers
- 1.2 Media Releases (& minority media sources)
- 1.3 Paid Advertising
- 1.4 Public Information Center
- 1.5 Public Meetings/Speakers Bureau
- 1.6 Project Telephone Hotline
- 1.7 Internet, E-Mail
- 1.8 Local cable TV and News
- 1.9 Notification to Impacted groups  
(i.e. bicycle users, pedestrians with disabilities, others)
- 1.10 Project Web Page
- 1.11 Caltrans Public Information Office
- 1.12 Consultant Public Information Office
- 1.13 Other items

X				RE to hand-deliver to business/residences.		X
X						X
		X				
	X			See comments below.		
X				Designer to add to budget if public meeting is added.		
	X					
	X					
X				Designer to verify impacted groups.		X
		X				
X				Items 1.1 to 1.11 to be handled by CT PIO.	\$40K	X
		X				
		X				

**2.0 Traveler Information Strategies**

- 2.1 Changeable Message Signs (permanent)
- 2.2 Changeable Message Signs (portable)
- 2.3 Special Construction Signs
- 2.4 Traveler Information Systems (CHIN/Internet)
- 2.5 Highway Advisory Radio "HAR" (fixed or mobile)
- 2.6 Radar Speed Sign
- 2.7 Traffic Management Team
- 2.8 Revised Transit Schedules/ Maps
- 2.9 Bicycle community information
- 2.10 Other items

	X			AS NEEDED		X
X				See comments below	\$95K	X
	X					X
X				As required.		X
X				For Full closures		X
		X				
	X			AS NEEDED PER CLOSURE		X
		X				
X				Same as Item 1.9.		X
		X				

**3.0 Incident Management**

- 3.1 COZEEP
- 3.2 Freeway Service Patrol (tow truck service patrol)
- 3.3 Transportation Management Center
- 3.4 Traffic Control Inspector (Caltrans)
- 3.5 Traffic Management Team
- 3.6 On-site Traffic Advisor (contractor)
- 3.7 Other Items

X				See comments below	\$658K	X
		X				
X						X
	X					
	X			As needed.		
	X					
		X				

**4.0 Construction Strategies**

- 4.1 Delay damage clause
- 4.2 Night work
- 4.3 Weekend Work
- 4.4 Extended Weekend Closures (55 Hr)
- 4.5 Planned Lane Closures
- 4.6 Planned Ramp Closures/Connector Closure
- 4.7 Total Facility Closure ( crossed-over )
- 4.8 Project Phasing
- 4.9 Truck Traffic Restrictions
- 4.10 Reduced Lane Widths
- 4.11 Temporary K-Rail
- 4.12 Temporary Traffic Screens
- 4.13 Regulatory Temporary Traffic Control Speed Zone
- 4.14 Traffic Control Improvements

X				Determine during PS&E	TBD	X
X				Per Lane Closure Charts		X
X				Per Lane Closure Charts		X
X				Per Lane Closure Charts		X
X				Per Lane Closure Charts.		X
X				Per Lane Closure Charts.		X
X				Per Lane Closure Charts.		X
X				Per Lane Closure Charts.		X
X				As per stage construction if any.		X
		X				
X				Per drawings/data sheet if any.		X
X				Project Engineer to determine		X
X				Project Engineer to determine as needed		X
	X			No request submitted		
X				As necessary.		X

**4.0 Construction Strategies (Continued)**

- 4.15 Contingency Plans
  - 4.15.1 Material Plant on standby
  - 4.15.2 Extra Critical Equipment on site
  - 4.15.3 Material Testing Plan
  - 4.15.4 Alternate Material on site  
(In case of failure or major delays)
  - 4.15.5 Emergency Detour Plan
  - 4.15.6 Emergency Notification Plan
  - 4.15.7 Weather Conditions Plan
  - 4.15.8 Delay Timing and Documentation Plan
  - 4.15.9 Late Closure Reopening Notification
- 4.16 Signal timing modification
- 4.17 Coordination with adjacent construction
- 4.18 Double Fine Zone (signs)
- 4.19 Right of Way Delay
- 4.20 ADA access to Pedestrian Facilities
- 4.21 Provide Pedestrians Access
- 4.22 Provide Bicyclists Access
- 4.23 Structure Strategies for Traffic Handling Constraints
- 4.24 Other Items

REQUIRED	RECOMMENDED	NOT APPLICABLE	BEES Item No.	COMMENTS	ITEM COST	REQUIRED IN SPEC.
X				Construction to determine items 4.15.1 thru. 4.15.9		X
		X				
X				RE to confirm prior to scheduling of closures.		X
		X				
		X				
X				See comments below.		X
X				Complete Street Guidelines		X
X				Complete Street Guidelines		X
X						X
X				See comments below.		X

**5.0 Demand Management**

- 5.1 HOV Lanes/Ramps
- 5.2 Ramp metering
- 5.3 Park-and-Ride Lots
- 5.4 Parking Management/Pricing
- 5.5 Rideshare Incentives
- 5.6 Rideshare Marketing
- 5.7 Transit, Train, or Light-Rail Incentives
- 5.8 Transit Service Modification
- 5.9 Variable Work Hours
- 5.10 Telecommute

		X				
		X				
		X				
		X				
		X				
		X				
		X				
		X				
		X				
		X				

**6.0 Alternate Route Strategies**

- 6.1 Ramp Closures
- 6.2 Street Improvements
- 6.3 Reversible Lanes
- 6.4 Temporary Lanes or Shoulders Use
- 6.5 Freeway to freeway connector closures
- 6.6 Other Items ( crossed-over )

X						X
		X				
		X				
X						X
X						X
X						X

**7.0 Other Strategies**

- 7.1 Application of new technology
- 7.2 District Lane Closure Review Committee (LCRC)
- 7.3 Construct ITS Elements
  - 7.3.1 Changeable Message Sign (CMS)
  - 7.3.2 Closed-Circuit Television (CCTV)
  - 7.3.3 Extinguishable Message Sign (EMS)
  - 7.3.4 Highway Advisory Radio (HAR) & Signs
  - 7.3.5 Ramp Metering
  - 7.3.6 Traffic Monitoring Station (TMS)
  - 7.3.7 Weather Station (RWIS)
- 7.4 Anti-Theft Prevention Strategies
- 7.5 Other Items

X						X
		X		No request submitted		
		X				
		X				
		X				
		X				
		X				
		X				
		X				
X				See Guidelines of Effective & Practical Wire Theft Prevention Strategies		X
		X				

**Comments:**

- 1.4 Plan, progress/completion information should be available at Local Public Works, Chamber of Commerce Offices, and CT Maintenance Offices.
- 1.9 Impacted groups need to be notified and informed about upcoming construction. During construction, access across job site will be needed.
- 1.11 PIO estimated at \$4K/mo. X 10 MO = \$40K (The rate is double of normal due to more complex lane closures on this project.)
- 2.2 PCMS Estimate: 2 PCMS@7K per month X10 MO.= \$70K + \$ 25 K LS for 12/ 55 HR closures=\$95 K TOTAL.
- 3.1 COZEEP Estimate: 2CHP/unit(2unit)(\$120/hr)(10hr/day)(86 day) = \$412,800 + \$244.8K for full or complex closures = \$657.6, say 658k
- 4.20 Ensure that temporary routes, which are provided around and through construction along pedestrian facilities under Caltrans jurisdiction, are accessible to persons with disabilities when provided.
- 4.24 RE/Inspector shall maintain access to all business & residences at all times.

**Approved by:**

Julio Hernandez

3/22/2018

For WILMAR KUHL, P.E. - TMP MANAGER

DATE

Chart No. G1 Freeway/Expressway Lane Requirements																											
County: San Joaquin										Route/Direction: 4/EB-WB										Post Mile: R15.5							
Closure limits: West Side crossover 0.1 mile East of Fresno Ave																											
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24		
Mon-Thu								1	1	1	1	1	1	1	1	1	1	1									
Fri								1	1	1	1	1	1	1	1												
Sat																											
Sun																											
Legend:																											
<p><b>Delete any legend not used.</b></p> <p><b>Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select <i>Split Cells</i>.</b></p> <p><b>Edit for the type of highway. Insert <i>freeway</i> or <i>expressway</i>.</b></p> <p><b>Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.</b></p>																											
<input type="checkbox"/> 1	Provide at least 1 through <u>Freeway</u> lane open in the direction of travel.																										
<input type="checkbox"/> 2	Provide at least 2 adjacent through <u>Freeway</u> lanes open in the direction of travel.																										
<input type="checkbox"/> 3	Provide at least 3 adjacent through <u>Freeway</u> lanes open in the direction of travel.																										
<input type="checkbox"/> 4	Provide at least 4 adjacent through <u>Freeway</u> lanes open in the direction of travel.																										
<input type="checkbox"/> 5	Provide at least 5 adjacent through <u>Freeway /Expressway</u> lanes open in the direction of travel.																										
<input type="checkbox"/> S	Shoulder closure is allowed (right / left).																										
<input type="checkbox"/> N	No work is allowed.																										
<input type="checkbox"/>	Work is allowed within the highway where a shoulder or lane closure is not required.																										
REMARKS:																											
<ol style="list-style-type: none"> <li>See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.</li> <li>Closures of local roads will require City/County concurrence.</li> <li>This chart is for the Construction and removal of the crossover including the K-Rail on the West end.</li> </ol>																											

Chart No. G2 Freeway/Expressway Lane Requirements																										
County: San Joaquin							Route/Direction: 4/EB-WB							Post Mile: R16.6												
Closure limits: East Side crossover near Center Street structure.																										
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mon-Thu	1	1	1	1	1	1																	1	1	1	
Fri	1	1	1	1	1	1																				
Sat																										
Sun																							1	1	1	

Legend:

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for the type of highway. Insert *freeway* or *expressway*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

**1** Provide at least 1 through Freeway lane open in the direction of travel.

**2** Provide at least 2 adjacent through Freeway lanes open in the direction of travel.

**3** Provide at least 3 adjacent through Freeway lanes open in the direction of travel.

**4** Provide at least 4 adjacent through Freeway lanes open in the direction of travel.

**5** Provide at least 5 adjacent through Freeway /Expressway lanes open in the direction of travel.

**S** Shoulder closure is allowed (right / left).

**N** No work is allowed.

Work is allowed within the highway where a shoulder or lane closure is not required.

REMARKS:

1. See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
2. Closures of local roads will require City/County concurrence.
3. This chart is for the Construction and removal of the crossover including the K-Rail on the East end.

Chart No. G3 Freeway/Expressway Lane Requirements																									
County: San Joaquin							Route/Direction: 4/EB-WB							Post Mile: R15.5 / R16.6											
Closure limits: 0.1 mile East of Fresno Ave to Center St.																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon–Thu	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Fri	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Sat	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Sun	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

Legend:

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for the type of highway. Insert *freeway* or *expressway*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

**1** Provide at least 1 through Freeway lane open in the direction of travel.

**2** Provide at least 2 adjacent through Freeway lanes open in the direction of travel.

**3** Provide at least 3 adjacent through Freeway lanes open in the direction of travel.

**4** Provide at least 4 adjacent through Freeway lanes open in the direction of travel.

**5** Provide at least 5 adjacent through Freeway /Expressway lanes open in the direction of travel.

**S** Shoulder closure is allowed (right / left).

**N** No work is allowed.

Work is allowed within the highway where a shoulder or lane closure is not required.

REMARKS:

- See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
- Closures of local roads will require City/County concurrence.
- Above window allows Eastbound lane to cross-over to the Westbound direction and vice versa to be completed within 30 working days per direction per stage construction



number, starting with I1. Use additional charts as needed and number them I2, I3, I4, etc. Change *chart* to *charts* if additional charts are added.

Comply with the requirements for the Complete Connector Closure Hours shown in the following chart:

<b>Chart No. I1</b>																									
<b>Complete Connector Closure Hours</b>																									
County: San Joaquin							Route/Direction: 5/NB-SB, 4/EB-WB							Post Mile: Various											
Closure limits: Connectors B,C, E, and F																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu	C	C	C	C	C	C	C															C	C	C	C
Fri	C	C	C	C	C	C	C																		
Sat																									
Sun																						C	C	C	C

Legend:

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

1	Provide at least 1 connector lane open in the direction of travel.
2	Provide at least 2 adjacent connector lanes open in the direction of travel.
C	Connector may be closed completely.
S	Shoulder closure is allowed (right/left).
N	No work is allowed.
	Work is allowed within the highway where a shoulder or lane closure is not required.

**Specify the detour route or reference the applicable detour or traffic handling plans.**

REMARKS:

1. See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
2. 7-day advance notice required.
3. No two consecutive or opposing connectors may be closed at the same time.
4. Detour required ( See Detour Plan or Motorist Information Plan )
5. Closures of local roads will require City/County concurrence.

**2. Use for a complete connector closure or a connector lane closure in District 7. Edit the introductory clause and chart title for the type of closure. Insert connector lane closure or complete connector closure in the introductory clause. For the**

number, starting with I1. Use additional charts as needed and number them I2, I3, I4, etc. Change *chart* to *charts* if additional charts are added.

Comply with the requirements for the Complete Connector Closure Hours shown in the following chart:

Chart No. I2 Complete Connector Closure Hours																									
County: San Joaquin							Route/Direction: 5/NB-SB, 4/EB-WB							Post Mile Various											
Closure limits: Connectors A,D,G, H																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon– Thu	C	C	C	C	C																		C	C	C
Fri	C	C	C	C	C																				
Sat																									
Sun																							C	C	C

Legend:

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

**1** Provide at least 1 connector lane open in the direction of travel.

**2** Provide at least 2 adjacent connector lanes open in the direction of travel.

**C** Connector may be closed completely.

**S** Shoulder closure is allowed (right/left).

**N** No work is allowed.

Work is allowed within the highway where a shoulder or lane closure is not required.

**Specify the detour route or reference the applicable detour or traffic handling plans.**

REMARKS:

- See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
- 7-day advance notice required.
- No two consecutive or opposing connectors may be closed at the same time.
- Detour required ( See Detour Plan or Motorist Information Plan )
- Closures of local roads will require City/County concurrence.

**2. Use for a complete connector closure or a connector lane closure in District 7. Edit the introductory clause and chart title for the type of closure. Insert connector lane closure or complete connector closure in the introductory clause. For the**

number, starting with I1. Use additional charts as needed and number them I2, I3, I4, etc. Change *chart* to *charts* if additional charts are added.

Comply with the requirements for the Complete Connector Closure Hours shown in the following chart:

Chart No. I3 Complete Connector Closure Hours																									
County: San Joaquin					Route/Direction: 5/NB-SB, 4/EB-WB										Post Mile: Various										
Closure limits: Various Connector/ramps and locations per stage Construction.																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon	C	C	C	C	C																				
Tue-Thu																									
Fri																								C	C
Sat	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sun	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C

Legend:

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

1 Provide at least 1 connector lane open in the direction of travel.

2 Provide at least 2 adjacent connector lanes open in the direction of travel.

C Connector may be closed completely.

S Shoulder closure is allowed (right/left).

N No work is allowed.

Work is allowed within the highway where a shoulder or lane closure is not required.

**Specify the detour route or reference the applicable detour or traffic handling plans.**

REMARKS:

1. See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
2. 7-day advance notice required.
3. No two consecutive or opposing connectors may be closed at the same time.
4. Detour required ( See Detour Plan or Motorist Information Plan )
5. Closures of local roads will require City/County concurrence.

number, starting with I1. Use additional charts as needed and number them I2, I3, I4, etc. Change *chart* to *charts* if additional charts are added.

Comply with the requirements for the Connector Lane Requirements shown in the following chart:

Chart No. I4																									
<u>Connector Lane Requirements</u>																									
County: San Joaquin							Route/Direction: 4/WB							Post 16.5 / 16.2											
Closure limits: Connectors D and H ( 3 lane segment)																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon– Thu	1	1	1	1	2																		2	1	1
Fri	1	1	1	1	2																				
Sat																									
Sun																						2	1	1	

Legend:

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

**1** Provide at least 1 connector lane open in the direction of travel.

**2** Provide at least 2 adjacent connector lanes open in the direction of travel.

**C** Connector may be closed completely.

**S** Shoulder closure is allowed (right/left).

**N** No work is allowed.

Work is allowed within the highway where a shoulder or lane closure is not required.

**Specify the detour route or reference the applicable detour or traffic handling plans.**

REMARKS:

1. See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
2. 7-day advance notice required.
3. No two consecutive or opposing connectors may be closed at the same time.
4. Detour required ( See Detour Plan or Motorist Information Plan )
5. Closures of local roads will require City/County concurrence.
6. Mainline Westbound Route 4 thru Navy Drive shall remain open.

number, starting with I1. Use additional charts as needed and number them I2, I3, I4, etc. Change *chart* to *charts* if additional charts are added.

Comply with the requirements for the Connector Lane Requirements shown in the following chart:

Chart No. I5 Connector Lane Requirements																									
County: San Joaquin										Route/Direction: 5/NB-SB, 4/EB-WB										Post VARIOUS					
Closure limits: Connectors B,C,E and F																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon– Thu	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Fri	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sat	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sun	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Legend:																									
Delete any legend not used.																									
Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select <i>Split Cells</i> .																									
Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.																									
1	Provide at least 1 connector lane open in the direction of travel.																								
2	Provide at least 2 adjacent connector lanes open in the direction of travel.																								
C	Connector may be closed completely.																								
S	Shoulder closure is allowed (right/left).																								
N	No work is allowed.																								
	Work is allowed within the highway where a shoulder or lane closure is not required.																								
Specify the detour route or reference the applicable detour or traffic handling plans.																									
REMARKS:																									
1. See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.																									
2. 10-day advance notice required.																									
3. No two consecutive or opposing connectors may be closed at the same time.																									
4. Detour required ( See Detour Plan or Motorist Information Plan )																									
5. Closures of local roads will require City/County concurrence.																									
6. Among Connectors, only one connector closure at a time per stage construction.																									

**Insert the chart number, starting with J1. Use additional charts as needed and number them J2, J3, J4, etc. Change *chart* to *charts* if additional charts are added.**

Comply with the requirements for the Complete Ramp Closure Hours shown in the following chart:

Chart No. J1 Complete Ramp Closure Hours																									
County: San Joaquin							Route/Direction: 4/EB-WB							Post Mile: 16.02, 16.06											
Closure limits: WB on ramp from Lincoln St. and EB off ramp to Lincoln St. (Ramps K and L)																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Fri	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sat	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sun	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Legend:																									
<p><b>Delete any legend not used.</b></p> <p><b>Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select <i>Split Cells</i>.</b></p> <p><b>Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.</b></p>																									
<input type="checkbox"/> 1	Provide at least 1 ramp lane, not less than 11 feet in width, open in the direction of travel.																								
<input type="checkbox"/> 2	Provide at least 2 adjacent ramp lanes open in the direction of travel.																								
<input type="checkbox"/> C	Ramp may be closed completely.																								
<input type="checkbox"/> S	Shoulder closure is allowed (right/left).																								
<input type="checkbox"/> N	No work is allowed.																								
<input type="checkbox"/>	Work is allowed within the highway where a shoulder or lane closure is not required.																								
<p align="center"><b>Specify the detour route or reference the applicable detour or traffic handling plans.</b></p>																									
REMARKS:																									
<ol style="list-style-type: none"> <li>See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.</li> <li>7-day advance notice required.</li> <li>No two consecutive or opposing ramps may be closed at the same time.</li> <li>Detoured required ( See Detour Plan or Motorist Information Plan )</li> <li>Closures of local roads will require City/County concurrence.</li> </ol>																									

**Note to Design:**

- Above window must be re-evaluated or updated if actual construction takes place later than 2021.
- Detour Plan required



**Insert the chart number, starting with J1. Use additional charts as needed and number them J2, J3, J4, etc. Change *chart* to *charts* if additional charts are added.**

Comply with the requirements for the Complete Ramp Closure Hours shown in the following chart:

<b>Chart No. J2</b>																									
<u>Complete Ramp Closure Hours</u>																									
County: San Joaquin							Route/Direction: 4/WB							Post Mile: 16.475											
Closure limits: On from Center St.(Ramp M)																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon–Thu	C	C	C	C	C																		C	C	C
Fri	C	C	C	C	C																				
Sat																									
Sun																							C	C	C

**Legend:**

**Delete any legend not used.**

**Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select *Split Cells*.**

**Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.**

1 Provide at least 1 ramp lane, not less than 11 feet in width, open in the direction of travel.

2 Provide at least 2 adjacent ramp lanes open in the direction of travel.

C Ramp may be closed completely.

S Shoulder closure is allowed (right/left).

N No work is allowed.

Work is allowed within the highway where a shoulder or lane closure is not required.

**Specify the detour route or reference the applicable detour or traffic handling plans.**

**REMARKS:**

1. See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.
2. 7-day advance notice required.
3. No two consecutive or opposing ramps may be closed at the same time.
4. Detoured required ( See Detour Plan or Motorist Information Plan )
5. Closures of local roads will require City/County concurrence.

**Note to Design:**

1. Above window must be re-evaluated or updated if actual construction takes place later than 2021.
2. Detour Plan required

Insert the chart number, starting with J1. Use additional charts as needed and number them J2, J3, J4, etc. Change *chart* to *charts* if additional charts are added.

Comply with the requirements for the Complete Ramp Closure Hours shown in the following chart:

Chart No. J3 Complete Ramp Closure Hours																									
County: San Joaquin							Route/Direction: 4/WB							Post Mile: 16.475											
Closure limits: On from Center St. Per stage construction.																									
Hour	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mon-Thu	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Fri	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sat	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
Sun	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C	C
<p>Legend:</p> <p><b>Delete any legend not used.</b></p> <p><b>Do not use shading or crosshatching. Half-hour increments can be accomplished by splitting the appropriate cell. Place the cursor inside the cell, right click on the mouse, and select <i>Split Cells</i>.</b></p> <p><b>Edit for a right or left shoulder closure. Do not edit if both shoulder closures apply.</b></p> <p><input type="checkbox"/> 1 Provide at least 1 ramp lane, not less than 11 feet in width, open in the direction of travel.</p> <p><input type="checkbox"/> 2 Provide at least 2 adjacent ramp lanes open in the direction of travel.</p> <p><input type="checkbox"/> C Ramp may be closed completely.</p> <p><input type="checkbox"/> S Shoulder closure is allowed (right/left).</p> <p><input type="checkbox"/> N No work is allowed.</p> <p><input type="checkbox"/> Work is allowed within the highway where a shoulder or lane closure is not required.</p> <p><b>Specify the detour route or reference the applicable detour or traffic handling plans.</b></p> <p>REMARKS:</p> <ol style="list-style-type: none"> <li>See Lane Closure Restrictions for Designated Holidays and Special Days table for additional closure restrictions.</li> <li>7-day advance notice required.</li> <li>No two consecutive or opposing ramps may be closed at the same time.</li> <li>Detoured required ( See Detour Plan or Motorist Information Plan )</li> <li>Closures of local roads will require City/County concurrence.</li> <li>Ramp K shall be open concurrently during the complete closure.</li> <li>Above work window to be completed within 5 working days</li> </ol>																									

**Note to Design:**

- Above window must be re-evaluated or updated if actual construction takes place later than 2021.
- Detour Plan required



Dist-County-Route: 10-SJ-4  
Post Mile Limits: R15.5/R16.7  
Project Type: Pavement Rehab (2R)  
Project ID (EA): 1016000026 (10-1C5000)  
Program Identification: 201.122  
Phase:  PID  PA/ED  PS&E

Regional Water Quality Control Board: Region 5, Central Valley, Sacramento Office  
Total Disturbed Soil Area: 25.90 acres PCTA: 25.90 acres  
Alternative Compliance (acres): TBD acres ATA 2 (50% Rule)? Yes  No   
Estimated Const. Start Date: 7/11/2020 Est Const. Complete: 1/5/2021  
Risk Level: RL 1  RL 2  RL 3  WPCP  Other: \_\_\_\_\_  
Is MWEL0 applicable? Yes  No   
Is the Project within a TMDL watershed? Yes  No   
TMDL Compliance Units (acres): 0.0  
Notification of ADL reuse (if yes, provide date): Yes  Date: \_\_\_\_\_ No

*This Report has been prepared under the direction of the following Licensed Person. The Licensed Person attests to the technical information contained herein and the date upon which recommendations, conclusions, and decisions are based. Professional Engineer or Landscape Architect stamp required at PS&E only.*

Kal Daher  
Kal Daher, Registered Project Engineer 4/25/18  
Date

I concur with the Construction water pollution control strategy and selected temporary BMPs in this report.

David Troop, date \_\_\_\_\_  
Construction SW Coordinator | I have reviewed the stormwater quality design issues and find this report to be complete, current and accurate:

Jes Padda  
for Jes Padda, Project Manager 4/25/18  
Date

Anthony Lertora  
Anthony Lertora, Maintenance Stormwater Coordinator 4-25-18  
Date

Brad Cole  
for Brad Cole, Landscape Architecture 4/25/18  
Date

James Espinosa, CR Env NPDES SW Branch Manager Date

**Caltrans Pavement Program  
 Pavement Condition Summary Report (PaveM)  
 BOTH DIRECTIONS; ALL LANES**

**District: 10; County: San Joaquin (SJ); Route: 4**

**From PM: 15.500 To PM: R16.600**

**L-Length: 1.762. R-Length: 1.694**

**L-Lane Miles: 2.695. R-Lane Miles: 2.404 (Unknown lane miles: 1.525)**

Year/ Condition Lane Miles	Traditional Condition (lane miles)						Assumed MAP-21 Condition (lane miles)			Total Lane Miles	Effectiveness (%)	
	Green	Yellow	Blue	Orange	Red	Good	Fair	Poor	SHOPP Effectiveness ((Red + Orange) /Total Lane Miles) %		Rehab Effectiveness (Red/Total Lane Miles) %	
2015	0.892	0.245	0.912	0.362	2.688	0.000	2.411	2.688	5.099	59.82	52.72	
2016	0.892	0.245	0.912	0.362	2.688	0.000	2.411	2.688	5.099	59.82	52.72	
2017	0.000	1.137	0.912	0.362	2.688	0.000	2.166	2.933	5.099	59.82	52.72	
2018	0.000	0.892	0.912	0.607	2.688	0.000	1.921	3.178	5.099	64.62	52.72	
2019	0.000	0.892	0.211	1.308	2.688	0.000	1.465	3.634	5.099	78.37	52.72	
2020	0.000	0.211	0.211	1.989	2.688	0.000	1.254	3.845	5.099	91.72	52.72	
2021	0.000	0.000	0.000	2.411	2.688	0.000	1.254	3.845	5.099	100.00	52.72	
2022	0.000	0.000	0.000	2.411	2.688	0.000	1.254	3.845	5.099	100.00	52.72	
2023	0.000	0.000	0.000	1.804	3.295	0.000	1.043	4.056	5.099	100.00	64.62	
2024	0.000	0.000	0.000	1.559	3.540	0.000	0.681	4.418	5.099	100.00	69.43	
2025	0.000	0.000	0.000	1.103	3.996	0.000	0.681	4.418	5.099	100.00	78.37	
2026	0.000	0.000	0.000	0.422	4.677	0.000	0.681	4.418	5.099	100.00	91.72	
2027	0.000	0.000	0.000	0.211	4.888	0.000	0.681	4.418	5.099	100.00	95.86	
2028	0.000	0.000	0.000	0.000	5.099	0.000	0.681	4.418	5.099	100.00	100.00	
2029	0.000	0.000	0.000	0.000	5.099	0.000	0.681	4.418	5.099	100.00	100.00	

## 2R PROJECT CERTIFICATION

A Safety Screening, as required by Design Information Bulletin Number 79-03, was conducted for the segment of highway identified above in the project description.



Mark Orr, Chief  
District 10 Traffic Engineering Branch

Date: 10-28-2015

This project will be scoped and designed as a 2R Project per the guidance in Design Information Bulletin Number 79-03. The Safety Screening that was performed will be an integral part of the development of this project.

Richard Helgeson, Central Region Office Chief  
Project Development Division – Design IV

Date: 11-30-2015

I concur with the 2R Purpose and Need of this project.

Paul Gennaro, District Design Coordinator

Date: 12-15-15

I concur that this project should be scoped and designed as a 2R Project per the guidance in Design Information Bulletin Number 79-03 and that the Safety Screening associated with this project will be an integral part of the development of this project. Therefore, since the appropriate Purpose and Need for this project is pavement resurfacing and restoration (2R), I have determined that this project is to be delivered as a 2R Project.

for Debra "Sam" Haack  
District 10 Deputy Director  
Maintenance and Operations

Date: 12-21-2015



LEVEL 2 - RISK REGISTER		Project Name:		SR-4 SJ Pavement Rehab		DIST- EA	10-1C500	Project Manager	Jes Padda							
Risk Identification						Risk Assessment						Risk Response				
Status	ID #	Type	Category	Title	Risk Statement	Current status/assumptions	Probability	Cost Impact	Cost Score	Time Impact	Time Score	Rationale	Strategy	Response Actions	Risk Owner	Updated
Active	1	Threat	Environmental	Cultural Resources	There is the potential to uncover cultural resources (example ADA ramp work).	Landscape in the project vicinity has been heavily modified in the past.	2-Low	4 -Moderate	8	4 -Moderate	8	Construction work will need to stop if cultural resources are found.	Accept	Further studies will be conducted in PA&ED and the scope will be refined. Once these cultural resources are found in Construction the impacts are unavoidable.	Zorayda Lao	4/13/2018
Active	2	Threat	Environmental	Hazardous Waste	If soil is exported, then a preliminary site investigation (PSI) will be required to test the soil for hazardous materials.	It is assumed that no soil will be exported from the project, as stated in the PEAR request.	2-Low	4 -Moderate	8	8 -High	16	An additional 400 hours and 6 months may be requested in order to conduct the PSI. There are disposal costs in a Hazardous Waste facility.	Avoid	Further studies will be conducted in PA&ED and the scope will be refined.	Zorayda Lao	4/13/2018
Retired	3	Threat	Environmental	Biological Environment	It is assumed any drainage work will only include minor modifications to existing drainage inlets.	If these modifications impact regulated waters, then permits will be required.	2-Low	2 -Low	4	8 -High	16	Permits will have impacts on the schedule greater than 6 months.	Avoid	Further studies will be conducted in PA&ED.	Zorayda Lao	4/13/2018
Active	4	Threat	Environmental	Biological Environment	If raptors or migratory bird species are observed nesting during pre-construction surveys, then biological monitoring may be required.	It is assumed Migratory Bird Treaty Act (MBTA) pre-construction surveys for nesting birds will be required if construction occurs between February 15th and September 1st.	2-Low	1 -Very Low	2	2 -Low	4	This is a low risk probability that could cost up to \$13,500 during construction.	Mitigate	Further studies will be conducted in PA&ED to see if this is still a risk. Preconstruction surveys will be required. Netting may be utilized to prevent nesting birds.	Zorayda Lao	4/13/2018
Active	5	Threat	Environmental	Biological Environment	If special status species are observed during surveys, then additional surveys and monitoring may be required.	No special status species assumed since the risk is low.	2-Low	4 -Moderate	4	4 -Moderate	4	This is a low risk probability that could have a moderate impact to cost.	Mitigate	Further studies will be conducted in PA&ED and the scope will be refined as needed.	Zorayda Lao	4/13/2018
Retired	6	Threat	Environmental	Environmental Document Changes	New information after Environmental Document is completed may require re-evaluation or a new document.	A Biological Opinion or a programmatic Biological Opinion are not needed. No sensitive environmental resources are present.	2-Low	2 -Low	4	2 -Low	4	A Categorical Exemption under CEQA and a Categorical Exclusion under NEPA are anticipated.	Avoid	Further studies will be conducted in PA&ED and the scope will be refined. Sensitive environmental resources should be avoided.	Zorayda Lao	4/13/2018
Active	7	Threat	Design	Ramp Closures	Stging plans, or rehabilitation strategy for high traffic volume connectors, need to be refined during PS&E.	Preliminary Staging Plans for high volume connectors were not accepted by Traffic Managemet. Extended weekend closures were also rejected.	4-High	4 -Moderate	16	4 -Moderate	16	This risk will impact project schedule and may impact scope and cost	Mitigate	If extended lane closures are not allowed to construct CRCP or CRCP-RSC pavement, the scope of work will need to be reduced to what can be constructed based on night-time closures only, such slab replacement only.	Kal Daher	3/19/2018
Active	8	Threat	Design	Design incomplete	Design incomplete	Design work is pending.	2-Low	4 -Moderate	8	2 -Low	4	Incomplete plans may result in cost increases in construction.	Avoid	Constructibility, QC/QA reviews, and Office Engineer reviews will be conducted.	Kal Daher	3/19/2018
Active	9	Threat	Design	Surveys incomplete	Not enough survey data to properly design project.	Survey pending.	2-Low	2 -Low	4	4 -Moderate	8	An incomplete will result in additional survey work and a delay in the project schedule.	Avoid	Coordinate with Surveys and Construction to ensure that there are not unnecessary delays.	Kal Daher	3/19/2018
Active	10	Threat	Design	Design Changes	New or revised design standard.	2R Certified project - Geometric Design Exceptions not required.	1-Very Low	2 -Low	2	2 -Low	2	New standards may add additional scope of work and impact the schedule and cost.	Avoid	Monitor. Request exception if needed.	Kal Daher	3/19/2018
Active	11	Threat	Design	Construction Schedule	Inaccurate contract time estimates	Design to develop accurate CPM working day schedule.	2-Low	8 -High	16	4 -Moderate	8	Errors in the CPM schedule will result in additional working days that will increase capital and support costs.	Avoid	Coordinate with Construction and OCER to ensure that there are adequate working days and the traffic handling is viable.	Kal Daher	3/19/2018
Active	12	Threat	PM	Support Costs	Underestimated support resources or overly optimistic delivery schedule.	Scope does not change and support costs and schedule are realistic. Some risk is built-in.	1-Very Low	8 -High	8	2 -Low	2	Functional units not properly resourced will result in higher support costs. Optimistic delivery schedule will also result in an overrun of support costs.	Avoid	Ensure that all appropriate functional units are resourced adequately. Monitor scope to ensure that these changes are covered by support cost increases.	Jes Padda	4/13/2018
Retired	13	Threat	PM	Goals	Inconsistent cost, time, scope, and quality objectives.	Cost, time, scope have been properly scoped and include adequate contingencies, risk, and schedule float.	2-Low	8 -High	16	4 -Moderate	8	Poor scope and inadequate cost and time will result big cost and time impacts.	Avoid	Monitor. Evaluate changes to minimize the impacts.	Jes Padda	4/13/2018
Retired	14	Threat	PM	Staffing	Losing critical staff at crucial point of the project.	Project teams to pick-up the slack when there are staffing changes.	1-Very Low	2 -Low	2	2 -Low	2	New staffing may have negative cost and time impacts.	Mitigate	Succession planning.	Jes Padda	4/13/2018
Active	15	Threat	ROW	R/W Changes	Late discovery utility work or permits.	No utility work or permits are expected.	1-Very Low	2 -Low	2	2 -Low	2	If there are no funds budgeted to R/W capital then it will be difficult to add these funds after programming.	Mitigate	Risk mitigation strategy to ensure that late discovery utilities and permits can be addressed.	Jes Padda	4/13/2018
Active	16	Threat	Design	Treatment of subgrade	Difficulty treating of the subbase in areas constructed under 54 hours.	Design will evaluate alternatives.	2-Low	2 -Low	4	8 -High	16	Lime treatment requires 3 days to cure and cement treated base requires 72 hours to cure.	Mitigate	Design, Materials, and Construction will develop a strategy to address this concern and maintain the planned design life.	Kal Daher	4/30/2018
Active	17	Threat	Design	Encountering utilities during subgrade construction	Unknown utilities such as electrical and irrigation lines could become damaged during subgrade construction.	Evaluate the need for additional potholing.	2-Low	2 -Low	4	8 -High	16	During construction of the subgrade, unknown utilities could be damaged requiring repair. If encountered during full closures, this risk has the potential to exceed the 54 hour full closure allotment.	Avoid	Design and Construction will consider additional potholing in either project development of in construction.	Kal Daher	4/30/2018
Retired	16	Threat	Organizational	Funding	Capital funding unavailable for construction.	Project will be programmed in 2018 SHOPP.	1-Very Low	4 -Moderate	4	4 -Moderate	4	Funding shortfalls result in inadequate funding for SHOPP.	Accept	Monitor. Options include downscope or delay the project.	Jes Padda	4/13/2018



STATE OF CALIFORNIA • DEPARTMENT OF TRANSPORTATION  
**RISK REGISTER CERTIFICATION (ACCOUNTABILITY CHECKPOINTS) FORM**  
 PPM-0001 (REV 07/2013)

District 10

The risk register is to be approved and signed-off by the District Deputies\* listed below for all scalability levels. By signing this form, you are certifying that you have reviewed the risks documented in the register and agree that they have been managed to the extent possible by the PDT.

**Project Information:**  Capital Project  Major Maintenance Project (Check One) Total Estimated Cost: \$ \_\_\_\_\_

Project ID/District-EA: 1016000026/10-1CS00

Project Description: SJ SR 4 Pavement Resurfacing and Restoration

Project Manager (PM): Jes Padda

Project Risk Manager (For Risk Level 3 Projects): \_\_\_\_\_

No Risk Register Certification Required -- Check box if project is less than \$1 million in total cost and risk register not prepared. Sign below and submit this form with PID, PA&ED, PS&E submittal, and RE Handoff File (as applicable).

Project Manager Signature: \_\_\_\_\_ Date: \_\_\_\_\_

**PA&ED (Required for Capital Projects Only)**

JES PADDA  
Project Manager Jes Padda Date: 4/27/18

NABEELAH ABI-RACHED  
Chief, Central Region Environmental Nabeelah Date: 5/1/18

*ps&e* BRIAN EVERSON  
Chief, Central Region Project Development Brian Date: 5/2/18

MONICA KRESS, Acting  
Deputy District Director, Program/Project Management Monika Date: 5/1/18

**Prior to PS&E (Required for Capital Projects and Major Maintenance Projects)**

JES PADDA  
Project Manager N/A Date: \_\_\_\_\_

BRIAN EVERSON  
\*Chief, Central Region Project Development N/A Date: \_\_\_\_\_

MARK DER MATOIAN  
Chief, Central Region Construction N/A Date: \_\_\_\_\_

JAMIE LUPO  
Chief, Central Region Right of Way N/A Date: \_\_\_\_\_

NABEELAH ABI-RACHED  
\*\*Chief, Central Region Environmental N/A Date: \_\_\_\_\_

MONICA KRESS, Acting  
Deputy District Director, Program/Project Management N/A Date: \_\_\_\_\_

\*or Deputy District Director - Maintenance & Operations signature for HM Projects designed by the District Maintenance Division  
 \*\*or Deputy District Director, Transportation Planning signature for HM Projects environmentally cleared by the District Environmental Stewardship Branch